

(01) Safety First(illustration) in Africa(1-247)

(01) Safety First(illustration) in Africa(1-247)

God Bless You !



I'll turn the desert
green



Come back safely



只野敏夫
TADANO TOSHIO

Reference

- | | | |
|---|--|--|
| 1 土木工学ハンドブック
Civil Engineering Handbook | 土木学会編
Edited by Japan Society of Civil Engineers | 技報堂
GIHODO SHUPPAN Co., Ltd. |
| 2 農業土木ハンドブック
Agricultural civil engineering handbook | 農業土木学会編
Japan Society of Agricultural Civil Engineers | 丸善株式会社
Maruzen Co., Ltd. |
| 3 林業土木ハンドブック
Forestry Civil Engineering Handbook | | 千代田出版
Chiyoda Publishing Co., Ltd. |
| 4 道路構造冷の解説と運用
Explanation and operation of road structure | (2003) | 社団法人 日本道路協会
Japan Road Association |
| 5 応用地質用語集
Glossary of applied geological terms | | 東洋書店
Toyo Shoten Co., Ltd. |
| 6 実用英和対訳 土木用語辞典
Practical English-Japanese translation Dictionary of civil engineering terms | | 工学出版株式会社
Engineering Publishing Co., Ltd. |
| 7 農業土木用語集
Glossary of agricultural civil engineering terms | | 東洋書店
Toyo Shoten Co., Ltd. |
| 8 土木施工用語集
Glossary of civil engineering construction terms | | 東洋書店
Toyo Shoten Co., Ltd. |
| 9 土木コンクリート用語集
Glossary of civil engineering and concrete terms | | 東洋書店
Toyo Book Book Store |
| 10 土木用語辞典
Dictionary of civil engineering terms | 東京工学研究会編
Edited by Tokyo Engineering Study Group | 工学出版株式会社
Engineering Publishing Co., Ltd. |
| 11 図解 土質・基礎用語集
Illustrated Glossary of Soil Characteristics and Basic Terms | | 東洋書店
Toyo Shoten Co., Ltd. |
| 12 図解テキスト 土木一般 (1-5)
Illustrated Text General civil engineering(1-5) | | 市ヶ谷出版社
ICHIGAYA Publishing Co., Ltd |
| 13 安全法令ダイジェスト
Safety Law Digest | | 労働新聞社
Labor Newspaper |

只野敏夫
Tadano Toshio

35 (S35) Occupational safety and health	Occupational safety and health
36 (S36) Occupational safety and health	Occupational safety and health
37 (S37) Occupational safety and health	Occupational safety and health
38 (S38) Occupational safety and health	Occupational safety and health
39 (S39) Work restrictions	Occupational safety and health
40 (S40) Work restrictions	Work restrictions
41 (S41) Work restrictions	Work restrictions
42 (S42) Work restrictions	Work restrictions
43 (S43) Work restrictions	Work restrictions
44 (S44) Work restrictions	Work restrictions
45 (S45) Work restrictions	Work restrictions
46 (S46) Work restrictions	Work restrictions
47 (S47) Work restrictions	Work restrictions
48 (S48) Work restrictions	Work restrictions
49 (S49) Notification of Plans	Work restrictions
50 (S50) Notification of Plans	Notification of Plans
51 (S51) Notification of Plans	Notification of Plans
52 (S52) Notification of Plans	Notification of Plans
53 (S53) Notification of Plans	Notification of Plans
54 (S54) Notification of Plans	Notification of Plans
55 (S55) Notification of Plans	Notification of Plans
56 (S56) Notification of Plans	Notification of Plans
57 (S57) Notification of Plans	Notification of Plans
58 (S58) Notification of Plans	Notification of Plans
59 (S59) Notification of Plans	Notification of Plans
60 (S60) Notification of Plans	Notification of Plans
61 (S61) Notification of Plans	Notification of Plans
62 (S62) Notification of Plans	Notification of Plans
63 (S63) Notification of Plans	Notification of Plans
64 (S64) Duties to be performed by specified principal contractors	Notification of Plans
65 (S65) Duties to be performed by specified principal contractors	Duties to be performed by specified principal contractors
66 (S66) Duties to be performed by specified principal contractors	Duties to be performed by specified principal contractors
67 (S67) Duties to be performed by specified principal contractors	Duties to be performed by specified principal contractors
68 (S68) Duties to be performed by specified principal contractors	Duties to be performed by specified principal contractors

69 (S69) Duties to be performed by specified principal contractors
70 (S70) Scaffolding
71 (S71) Scaffolding
72 (S72) Scaffolding
73 (S73) Scaffolding
74 (S74) Scaffolding
75 (S75) Scaffolding
76 (S76) Inspection of scaffolding
77 (S77) Inspection of scaffolding
78 (S78) Inspection of scaffolding
79 (S79) Inspection of scaffolding
80 (S80) Scaffolding
81 (S81) Scaffolding
82 (S82) Scaffolding
83 (S83) Scaffolding
84 (S84) Scaffolding
85 (S85) Scaffolding
86 (S86) Scaffolding
87 (S87) Scaffolding
88 (S88) Scaffolding
89 (S89) Scaffolding
90 (S90) Formwork and Shoring
91 (S91) Formwork and Shoring
92 (S92) Formwork and Shoring
93 (S93) Formwork and Shoring
94 (S94) Formwork and Shoring
95 (S95) Formwork and Shoring
96 (S96) Formwork and Shoring
97 (S97) Formwork and Shoring
98 (S98) Formwork and Shoring
99 (S99) Structure excavation-Structure - Excavation slope gradient
100 (S100) Structure excavation-Structure - Excavation slope gradient
101 (S101) Structure excavation-Structure - Excavation slope gradient
102 (S102) Safety measures for excavation work

Duties to be performed by specified principal contractors
Duties to be performed by specified principal contractors
Scaffolding
Scaffolding
Scaffolding
Scaffolding
Scaffolding
Scaffolding
Scaffolding
Inspection of scaffolding
Inspection of scaffolding
Inspection of scaffolding
Inspection of scaffolding
Scaffolding
Scaffolding
Scaffolding
Scaffolding
Scaffolding
Scaffolding
Scaffolding
Scaffolding
Scaffolding
Scaffolding
Scaffolding
Scaffolding
Scaffolding
Scaffolding
Scaffolding
Scaffolding
Scaffolding
Scaffolding
Scaffolding
Formwork and Shoring
Formwork and Shoring
Formwork and Shoring
Formwork and Shoring
Formwork and Shoring
Formwork and Shoring
Formwork and Shoring
Formwork and Shoring
Formwork and Shoring
Formwork and Shoring
Formwork and Shoring
Formwork and Shoring
Formwork and Shoring
Formwork and Shoring
Formwork and Shoring
Formwork and Shoring
Formwork and Shoring
Formwork and Shoring
Formwork and Shoring
Excavation slope gradient
Excavation slope gradient
Excavation slope gradient
Excavation slope gradient
Safety measures for excavation work

171 (S171) Public disaster	Public disaster
172 (S172) Workplace	Workplace
173 (S173) Workplace	Workplace
174 (S174) Workplace	Workplace
175 (S175) Workplace	Workplace
176 (S176)Traffic measures	Traffic measures
177 (S177)Traffic measures	Traffic measures
178 (S178)Traffic measures	Traffic measures
179 (S179)Traffic measures	Traffic measures
180 (S180)Traffic measures	Traffic measures
181 (S181)Buried Objects	Buried Objects
182 (S182)Buried Objects	Buried Objects
183 (S183)Buried Objects	Buried Objects
184 (S184)Buried Objects	Buried Objects
185 (S185)Buried Objects	Buried Objects
186 (S186)Buried Objects	Buried Objects
187 (S187)Buried Objects	Buried Objects
188 (S188)Retaining Works	Retaining Works
189 (S189)Retaining Works	Retaining Works
190 (S190)Retaining Works	Retaining Works
191 (S191)Retaining Works	Retaining Works
192 (S192)Retaining Works	Retaining Works
193 (S193)Covering work	Covering work
194 (S194)Covering work	Covering work
195 (S195)Gas disaster	Gas disaster
196 (S196)Gas disaster	Gas disaster
197 (S197)Gas disaster	Gas disaster
198 (S198)Gas disaster	Gas disaster
199 (S199)Gas disaster	Gas disaster
200 (S200)Workplace accidents	Workplace accidents
201 (S201)Workplace accidents	Workplace accidents
202 (S202)Workplace accidents	Workplace accidents
203 (S203)Workplace accidents	Workplace accidents
204 (S204)Safety management	Safety management

205 (S205) Safety management	Safety management
206 (S206) Safety management	Safety management
207 (S207) Safety management	Safety management
208 (S208) Safety management	Safety management
209 (S209) Safety management	Safety management
210 (S210) Safety management	Safety management
211 (S211) Safety management	Safety management
212 (S212) Safety management	Safety management
213 (S213) Safety management	Safety management
214 (S214) Safety management	Safety management
215 (S215) Safety management	Safety management
216 (S216) Safety management	Safety management
217 (S217) Safety management	Safety management
218 (S218) Safety management	Safety management
219 (S219) Safety management	Safety management
220 (S220) Safety management	Safety management
221 (S221) Prevent falling objects	Prevent falling objects
222 (S222) Prevent falling objects	Prevent falling objects
223 (S223) Prevent falling objects	Prevent falling objects
224 (S224) Prevent falling objects	Prevent falling objects
225 (S225) Prevent falling objects	Prevent falling objects
226 (S226) Prevent falling objects	Prevent falling objects
227 (S227) Prevent falling objects	Prevent falling objects
228 (S228) Mobile crane	Mobile crane
229 (S229) Mobile crane	Mobile crane
230 (S230) Mobile crane	Mobile crane
231 (S231) Mobile crane	Mobile crane
232 (S232) Mobile crane	Mobile crane
233 (S233) Mobile crane	Mobile crane
234 (S234) Mobile crane	Mobile crane
235 (S235) Mobile crane	Mobile crane
236 (S236) Mobile crane	Mobile crane
237 (S237) Public accidents	Public accidents
238 (S238) Public accidents	Public accidents

156 (S156) Accommodation	Accommodation
157 (S157) Accommodation	Accommodation
158 (S158) Accommodation	Accommodation
130 (S130) Blasting work	Blasting work
131 (S131) Blasting work	Blasting work
132 (S132) Blasting work	Blasting work
133 (S133) Blasting work	Blasting work
134 (S134) Blasting work	Blasting work
135 (S135) Blasting work	Blasting work
136 (S136) Blasting work	Blasting work
137 (S137) Blasting work	Blasting work
138 (S138) Blasting work	Blasting work
139 (S139) Blasting work	Blasting work
140 (S140) Blasting work	Blasting work
181 (S181) Buried Objects	Buried Objects
182 (S182) Buried Objects	Buried Objects
183 (S183) Buried Objects	Buried Objects
184 (S184) Buried Objects	Buried Objects
185 (S185) Buried Objects	Buried Objects
186 (S186) Buried Objects	Buried Objects
187 (S187) Buried Objects	Buried Objects
146 (S146) Caisson and Diving Box	Caisson and Diving Box
141 (S141) compressed air work	compressed air work
142 (S142) compressed air work	compressed air work
143 (S143) compressed air work	compressed air work
144 (S144) compressed air work	compressed air work
145 (S145) compressed air work	compressed air work
193 (S193) Covering work	Covering work
194 (S194) Covering work	Covering work
65 (S65) Duties to be performed by specified principal contractors	Duties to be performed by specified principal contractors
66 (S66) Duties to be performed by specified principal contractors	Duties to be performed by specified principal contractors
67 (S67) Duties to be performed by specified principal contractors	Duties to be performed by specified principal contractors
68 (S68) Duties to be performed by specified principal contractors	Duties to be performed by specified principal contractors
69 (S69) Duties to be performed by specified principal contractors	Duties to be performed by specified principal contractors

70 (S70) Scaffolding
106 (S106) Sheet pile installation
147 (S147) Electric Shock
148 (S148) Electric Shock
149 (S149) Electric Shock
109 (S109) Work platform
99 (S99) Structure excavation-Structure - Excavation slope gradient
100 (S100) Structure excavation-Structure - Excavation slope gradient
101 (S101) Structure excavation-Structure - Excavation slope gradient
150 (S150) Fall on
151 (S151) Fall on
152 (S152) Fall on
153 (S153) Fall on
90 (S90) Formwork and Shoring
91 (S91) Formwork and Shoring
92 (S92) Formwork and Shoring
93 (S93) Formwork and Shoring
94 (S94) Formwork and Shoring
95 (S95) Formwork and Shoring
96 (S96) Formwork and Shoring
97 (S97) Formwork and Shoring
98 (S98) Formwork and Shoring
195 (S195) Gas disaster
196 (S196) Gas disaster
197 (S197) Gas disaster
198 (S198) Gas disaster
199 (S199) Gas disaster
77 (S77) Inspection of scaffolding
78 (S78) Inspection of scaffolding
79 (S79) Inspection of scaffolding
80 (S80) Scaffolding
228 (S228) Mobile crane
229 (S229) Mobile crane
230 (S230) Mobile crane

Duties to be performed by specified principal contractors
Earth retaining support
Electric Shock
Electric Shock
Electric Shock
Excavation of tunnels
Excavation slope gradient
Excavation slope gradient
Excavation slope gradient
Fall on
Fall on
Fall on
Fall on
Formwork and Shoring
Formwork and Shoring
Formwork and Shoring
Formwork and Shoring
Formwork and Shoring
Formwork and Shoring
Formwork and Shoring
Formwork and Shoring
Formwork and Shoring
Formwork and Shoring
Formwork and Shoring
Gas disaster
Gas disaster
Gas disaster
Gas disaster
Gas disaster
Inspection of scaffolding
Inspection of scaffolding
Inspection of scaffolding
Inspection of scaffolding
Mobile crane
Mobile crane
Mobile crane

231 (S231) Mobile crane	Mobile crane
232 (S232) Mobile crane	Mobile crane
233 (S233) Mobile crane	Mobile crane
234 (S234) Mobile crane	Mobile crane
235 (S235) Mobile crane	Mobile crane
236 (S236) Mobile crane	Mobile crane
124 (S124) Mobile cranes	Mobile cranes
125 (S125) Track system	Mobile cranes
50 (S50) Notification of Plans	Notification of Plans
51 (S51) Notification of Plans	Notification of Plans
52 (S52) Notification of Plans	Notification of Plans
53 (S53) Notification of Plans	Notification of Plans
54 (S54) Notification of Plans	Notification of Plans
55 (S55) Notification of Plans	Notification of Plans
56 (S56) Notification of Plans	Notification of Plans
57 (S57) Notification of Plans	Notification of Plans
58 (S58) Notification of Plans	Notification of Plans
59 (S59) Notification of Plans	Notification of Plans
60 (S60) Notification of Plans	Notification of Plans
61 (S61) Notification of Plans	Notification of Plans
62 (S62) Notification of Plans	Notification of Plans
63 (S63) Notification of Plans	Notification of Plans
64 (S64) Duties to be performed by specified principal contractors	Notification of Plans
19 (S19) Occupational safety and health	Occupational safety and health
20 (S20) Occupational safety and health	Occupational safety and health
21 (S21) Occupational safety and health	Occupational safety and health
22 (S22) Occupational safety and health	Occupational safety and health
23 (S23) Occupational safety and health	Occupational safety and health
24 (S24) Occupational safety and health	Occupational safety and health
25 (S25) Occupational safety and health	Occupational safety and health
26 (S26) Occupational safety and health	Occupational safety and health
27 (S27) Occupational safety and health	Occupational safety and health
28 (S28) Occupational safety and health	Occupational safety and health
29 (S29) Occupational safety and health	Occupational safety and health

30 (S30) Occupational safety and health
31 (S31) Occupational safety and health
32 (S32) Occupational safety and health
33 (S33) Occupational safety and health
34 (S34) Occupational safety and health
35 (S35) Occupational safety and health
36 (S36) Occupational safety and health
37 (S37) Occupational safety and health
38 (S38) Occupational safety and health
39 (S39) Work restrictions
154 (S154) oxygen deficiency
155 (S155) oxygen deficiency
123 (S123) Mobile cranes
221 (S221) Prevent falling objects
222 (S222) Prevent falling objects
223 (S223) Prevent falling objects
224 (S224) Prevent falling objects
225 (S225) Prevent falling objects
226 (S226) Prevent falling objects
227 (S227) Prevent falling objects
237 (S237) Public accidents
238 (S238) Public accidents
239 (S239) Public accidents
240 (S240) Public accidents
241 (S241) Public accidents
242 (S242) Public accidents
243 (S243) Public accidents
244 (S244) Public accidents
245 (S245) Public accidents
246 (S246) Public accidents
247 (S247) Public accidents
159 (S159) Public disaster
160 (S160) Public disaster
161 (S161) Public disaster

Occupational safety and health
Occupational safety and health
Occupational safety and health
Occupational safety and health
Occupational safety and health
Occupational safety and health
Occupational safety and health
Occupational safety and health
Occupational safety and health
Occupational safety and health
Occupational safety and health
oxygen deficiency
oxygen deficiency
Pile drivers
Prevent falling objects
Prevent falling objects
Prevent falling objects
Prevent falling objects
Prevent falling objects
Prevent falling objects
Prevent falling objects
Prevent falling objects
Public accidents
Public accidents
Public accidents
Public accidents
Public accidents
Public accidents
Public accidents
Public accidents
Public accidents
Public accidents
Public accidents
Public accidents
Public disaster
Public disaster
Public disaster

205 (S205) Safety management	Safety management
206 (S206) Safety management	Safety management
207 (S207) Safety management	Safety management
208 (S208) Safety management	Safety management
209 (S209) Safety management	Safety management
210 (S210) Safety management	Safety management
211 (S211) Safety management	Safety management
212 (S212) Safety management	Safety management
213 (S213) Safety management	Safety management
214 (S214) Safety management	Safety management
215 (S215) Safety management	Safety management
216 (S216) Safety management	Safety management
217 (S217) Safety management	Safety management
218 (S218) Safety management	Safety management
219 (S219) Safety management	Safety management
220 (S220) Safety management	Safety management
102 (S102) Safety measures for excavation work	Safety measures for excavation work
103 (S103) Safety measures for excavation work	Safety measures for excavation work
104 (S104) Safety measures for excavation work	Safety measures for excavation work
105 (S105) Earth retaining support	Safety measures for excavation work
71 (S71) Scaffolding	Scaffolding
72 (S72) Scaffolding	Scaffolding
73 (S73) Scaffolding	Scaffolding
74 (S74) Scaffolding	Scaffolding
75 (S75) Scaffolding	Scaffolding
76 (S76) Inspection of scaffolding	Scaffolding
81 (S81) Scaffolding	Scaffolding
82 (S82) Scaffolding	Scaffolding
83 (S83) Scaffolding	Scaffolding
84 (S84) Scaffolding	Scaffolding
85 (S85) Scaffolding	Scaffolding
86 (S86) Scaffolding	Scaffolding
87 (S87) Scaffolding	Scaffolding
88 (S88) Scaffolding	Scaffolding

49 (S49) Notification of Plans
172 (S172) Workplace
173 (S173) Workplace
174 (S174) Workplace
175 (S175) Workplace
200 (S200) Workplace accidents
201 (S201) Workplace accidents
202 (S202) Workplace accidents
203 (S203) Workplace accidents

Work restrictions
Workplace
Workplace
Workplace
Workplace
Workplace accidents
Workplace accidents
Workplace accidents
Workplace accidents


(S1) Safety management

(S1) Safety management


3 Safety management

3-2 Workplace accidents


1 Accidents caused by falls




2 Accidents caused by construction machinery



3 Accidents caused by automobiles




4 Landslides and rockfalls



5 Collapse



6 Flying objects and falling objects



(S2) Safety management

(S2) Safety management

3 Safety management


3-2 Workplace accidents

3-2-3 Causes of accidents and countermeasures

1 Unsafe conditions


2 Unsafe actions

3 Unsafe human factors




C1051
M420

steel cylinder: shield



C1324
M367

Concrete spraying



M322

Pneumatic caisson

(S3) Safety management

(S3) Safety management

3 Safety management

3-2 Workplace accidents

3-2-3 Causes of accidents and countermeasures





Figure 3-1 Causes of accidents and countermeasures

(S4) Safety management





(S5) Safety management

(S5) Safety management

3 Safety management

3-2 Workplace accidents

3-2-3 Causes of accidents and countermeasures



M322

Pneumatic caisson

Figure 3-1 Causes of accidents and countermeasures


(S6) Safety management

(S6) Safety management

3 Safety management

3-2 Workplace accidents


1 Accidents caused by falls




3-2-4 Accident investigation

- 1) Accident cause - accurately
- 2) Chemically and objectively investigate
- 3) Comprehensive judgment
- 4) Record keeping


2 Accidents caused by construction machinery



3 Accidents caused by automobiles




4 Landslides and rockfalls



5 Collapse



6 Flying objects and falling objects



(S7) Safety management

(S7) Safety management

3 Safety Management


Table 3-1 List of work for which a supervisor should be appointed

3-3 Occupational Safety and Health

① High pressure indoor work

3-3-2 Appointment of Work Supervisor

- ② Pneumatic caisson
- Construction certainty
- Foundations of long bridges, etc.



M279

F109

(S8) Safety management

(S8) Safety management

3 Safety Management


3-3 Occupational Safety and Health

3-3-2 Appointment of Work Supervisor

Table 3-1 List of work for which a supervisor should be appointed

② Metal welding, melting or heating work using acetylene

Wet method underwater arc welding dry method



(S9) Safety management

(S9) Safety management


3 Safety Management

3-3 Occupational Safety and Health

3-3-2 Appointment of Work Supervisor

Table 3-1 List of work for which a supervisor should be appointed

③ Work using a concrete crusher



concrete and rock crushing

C1133
M425

(S10) Safety management

(S10) Safety management


3 Safety Management

3-3 Occupational Safety and Health

3-3-2 Appointment of Work Supervisor

Table 3-1 List of work for which a supervisor should be appointed

- ④ Excavation of ground with a height of 2m or more



E416

(S11) Safety management

(S11) Safety management


3 Safety Management

3-3 Occupational Safety and Health

3-3-2 Appointment of Work Supervisor

Table 3-1 List of work for which a supervisor should be appointed

⑤ Installation and removal of struts and ribs of earth retaining supports



Earth retaining wall method

E602

(S12) Safety management

(S12) Safety management

3 Safety Management



3-3 Occupational Safety and Health

3-3-2 Appointment of Work Supervisor

Table 3-1 List of work for which a supervisor should be appointed

㊦ Assembly and dismantling of formwork supports

Steel formwork
formwork made of steel



C1025

(S13) Safety management

(S13) Safety management

3 Safety Management

3-3 Occupational Safety and Health

3-3-2 Appointment of Work Supervisor


Table 3-1 List of work for which a supervisor should be appointed

- ⑦ Assembly and dismantling of suspended scaffolding, overhanging scaffolding, and scaffolding with a height of 5m or more

Concrete bridge(Erection)

Cast-in-place method

② Mobile shoring



(S14) Safety management

(S14) Safety management

3 Safety Management

3-3 Occupational Safety and Health

3-3-2 Appointment of Work Supervisor

Table 3-1 List of work for which a supervisor should be appointed

⑧ Assembly and dismantling of steel frames with a height of 5m or more

① moving rail

② anchors

③ wheels

④ workbench

⑤ workbench

⑥ formwork


⑦ rail anchor

⑧ concrete girder

⑨ wheels

moveable form carrier

mobile work vehicle



(S15) Safety management

(S15) Safety management


3 Safety Management

3-3 Occupational Safety and Health

3-3-2 Appointment of Work Supervisor

Table 3-1 List of work for which a supervisor should be appointed

- ⑨ Work in places where there is a risk of oxygen deficiency



airlock bucket caisson load water firm ground shaft working room

(S16) Safety management

(S16) Safety management

3 Safety Management


3-3 Occupational Safety and Health

3-3-2 Appointment of Work Supervisor

Table 3-1 List of work for which a supervisor should be appointed

⑩ Excavation work of tunnels, etc. or associated pile of rubble

Assembly of tunnel supports, installation of rock bolts, concrete spraying work



(S17) Safety management

(S17) Safety management


3 Safety Management

3-3 Occupational Safety and Health

3-3-2 Appointment of Work Supervisor

Table 3-1 List of work for which a supervisor should be appointed

- ① Covering work of tunnels, etc.



(S18) Safety management

(S18) Safety management


3 Safety Management

3-3 Occupational Safety and Health

3-3-2 Appointment of Work Supervisor

Table 3-1 List of work for which a supervisor should be appointed

- ② Dismantling or destruction of concrete structures with a height of 5m or more



M23
E229

(S19) Occupational safety and health

(S19) Occupational safety and health

3 Safety Management

3-3 Occupational Safety and Health

3-3-3 Safety and Health training

1. In case of a worker is hired (new hire training)
2. In case of the work content is changed (preparation for new hire training)

new hire training



Safety and Health training

(S20) Occupational safety and health

(S20) Occupational safety and health

3 Safety Management


3-3 Occupational Safety and Health

3-3-3 Safety satellite training

3. In case of a worker is assigned to dangerous or risky work (special training)

4. New foreman/foreman training (foreman training)

special training foreman training



P208-P211

F58
S15

(S21) Occupational safety and health

(S21) Occupational safety and health


3 Safety Management

3-3 Occupational Safety and Health

3-3-3 Safety satellite training

Table 3-2 Work requiring special training

① Welding work



M67
F101

(S22) Occupational safety and health

(S22) Occupational safety and health

3 Safety Management


3-3 Occupational Safety and Health

3-3-3 Safety satellite training

Table 3-2 Work requiring special training

② Driving forklifts weighing less than 1 ton

forklifts



(S23) Occupational safety and health

(S23) Occupational safety and health


3 Safety Management

3-3 Occupational Safety and Health

3-3-3 Safety satellite training

Table 3-2 Work requiring special training

③ Driving bulldozers weighing less than 3 ton



(S24) Occupational safety and health

(S24) Occupational safety and health


3 Safety Management

3-3 Occupational Safety and Health


3-3-3 Safety satellite training

Table 3-2 Work requiring special training


④ Driving compaction machines such as rollers



road roller



tire roller



vibrating roller

(S25) Occupational safety and health

(S25) Occupational safety and health


3 Safety Management

3-3 Occupational Safety and Health

3-3-3 Safety satellite training

Table 3-2 Work requiring special training

⑤ Driving powered hoists, etc.



M338

(S26) Occupational safety and health

(S26) Occupational safety and health

3 Safety Management


3-3 Occupational Safety and Health

3-3-3 Safety satellite training

Table 3-2 Work requiring special training


⑥ Driving powered pile drivers, etc.

Diesel hammer



F38

Vibrohammer



F101

(S27) Occupational safety and health

(S27) Occupational safety and health


3 Safety Management

3-3 Occupational Safety and Health

3-3-3 Safety satellite training

Table 3-2 Work requiring special training

- ⑦ Driving track equipment, etc.



aerial cableway

E232

(S28) Occupational safety and health

(S28) Occupational safety and health


3 Safety Management

3-3 Occupational Safety and Health

3-3-3 Safety satellite training

Table 3-2 Work requiring special training

Ⓞ Driving cranes with a lifting capacity of less than 5 ton



E289
M138

(S29) Occupational safety and health

(S29) Occupational safety and health


3 Safety Management

3-3 Occupational Safety and Health

3-3-3 Safety satellite training

Table 3-2 Work requiring special training

⑨ Driving mobile cranes with a lifting capacity of less than 1 ton



B111

M46

(S30) Occupational safety and health

(S30) Occupational safety and health


3 Safety Management

3-3 Occupational Safety and Health

3-3-3 Safety satellite training

Table 3-2 Work requiring special training

⑩ Driving machines with a lifting capacity of less than 5 ton derrick operation work



B417
M49

(S31) Occupational safety and health

(S31) Occupational safety and health


3 Safety Management

3-3 Occupational Safety and Health

3-3-3 Safety satellite training

Table 3-2 Work requiring special training

① Construction lift operation work



(S32) Occupational safety and health

(S32) Occupational safety and health




3 Safety Management

3-3 Occupational Safety and Health

3-3-3 Safety satellite training

Table 3-2 Work requiring special training

② Sling operation work for cranes and mobile cranes with a lifting capacity of less than 1t



(S33) Occupational safety and health


(S33) Occupational safety and health

3 Safety Management

3-3 Occupational Safety and Health

3-3-3 Safety satellite training

Table 3-2 Work requiring special training



(S34) Occupational safety and health

(S34) Occupational safety and health

3 Safety Management


3-3 Occupational Safety and Health

3-3-3 Safety satellite training

Table 3-2 Work requiring special training

④ Operation work such as adjusting the air supply to high-pressure work rooms

air compressor
Prepare for emergencies by having two or more power sources



(S35) Occupational safety and health

(S35) Occupational safety and health


3 Safety Management

3-3 Occupational Safety and Health

3-3-3 Safety satellite training

Table 3-2 Work requiring special training

- ⑤ Operation work such as adjusting the air supply to divers



P208-P211

(S36) Occupational safety and health

(S36) Occupational safety and health


3 Safety Management

3-3 Occupational Safety and Health

3-3-3 Safety satellite training

Table 3-2 Work requiring special training

ⓐ Work related to dangerous work involving oxygen deficiency



(S37) Occupational safety and health

(S37) Occupational safety and health


3 Safety Management

3-3 Occupational Safety and Health

3-3-3 Safety satellite training

Table 3-2 Work requiring special training

① Work related to work inside high-pressure rooms



S15
F59
M262

(S38) Occupational safety and health

(S38) Occupational safety and health


3 Safety Management

3-3 Occupational Safety and Health

3-3-3 Safety satellite training

Table 3-2 Work requiring special training

- ⑧ Excavation work for tunnels, etc. or the transportation of waste materials associated with this Work related to pouring concrete for covering works, etc.
(Limited to work carried out inside tunnels, etc.)



T255

T45

(S39) Work restrictions

(S39) Work restrictions


3 Safety management

3-3 Occupational safety and health

3.3.4 Work restrictions

Table 3.3 List of work related to work restrictions

- ① Work related to drilling, loading, wiring, ignition, and inspection
and disposal of unexploded equipment



(S40) Work restrictions

(S40) Work restrictions

3 Safety management


3-3 Occupational safety and health

3.3.4 Work restrictions

Table 3.3 List of work related to work restrictions

② Work handling boilers (excluding small boilers)

dipper dredger



R432

(S41) Work restrictions

(S41) Work restrictions


3 Safety management

3-3 Occupational safety and health

3.3.4 Work restrictions

Table 3.3 List of work related to work restrictions

③ Work operating cranes with a lifting capacity of 5t or more



(S42) Work restrictions

(S42) Work restrictions


3 Safety management

3-3 Occupational safety and health

3.3.4 Work restrictions

Table 3.3 List of work related to work restrictions

④ Work operating mobile cranes with a lifting capacity of 5t or more



M138

B111

(S43) Work restrictions

(S43) Work restrictions


3 Safety management

3-3 Occupational safety and health

3.3.4 Work restrictions

Table 3.3 List of work related to work restrictions

- ⑤ Work operating derricks with a lifting capacity of 5t or more



B417
M49

(S44) Work restrictions

(S44) Work restrictions


3 Safety management

3-3 Occupational safety and health

3.3.4 Work restrictions

Table 3.3 List of work related to work restrictions

⑥ Underwater work using a diving device and receiving air from an air compressor, etc.



(S45) Work restrictions

(S45) Work restrictions

3 Safety management


3-3 Occupational safety and health

3.3.4 Work restrictions

Table 3.3 List of work related to work restrictions

⑦ Work welding, cutting, or heating metals using flammable gases, etc.

underwater gas cutting



(S46) Work restrictions

(S46) Work restrictions

3 Safety management


3-3 Occupational safety and health

3.3.4 Work restrictions

Table 3.3 List of work related to work restrictions

⊗ Work operating forklifts with a maximum load of 1t or more

forklifts



(S47) Work restrictions

(S47) Work restrictions


3 Safety management

3-3 Occupational safety and health

3.3.4 Work restrictions


Table 3.3 List of work related to work restrictions

⊕ Work operating self-propelled construction machinery with a machine weight of 3t or more



Crawler type tractor excavator

E291



tractor excavator

E292

(S48) Work restrictions

(S48) Work restrictions


3 Safety management

3-3 Occupational safety and health

3.3.4 Work restrictions truck crane

Table 3.3 List of work related to work restrictions

Ⓢ Slinging work for cranes, mobile cranes, and derricks with a lifting capacity of 1t or more
tower crane



(S49) Notification of Plans


(S49) Notification of Plans

3 Safety Management

3-3 Occupational Safety and Health

3.3.5 Notification of Plans

- ① Construction that must be notified to the Minister of Labor 30 days before construction begins
 - s49 Construction of structures over 300m in height



(S50) Notification of Plans


(S50) Notification of Plans

3 Safety Management

3-3 Occupational Safety and Health

3.3.5 Notification of Plans

- ① Construction that must be notified to the Minister of Labor 30 days before construction begins
 - s50 Construction of dams with a height of 150m or more



(S51) Notification of Plans

(S51) Notification of Plans


3 Safety Management

3-3 Occupational Safety and Health


3.3.5 Notification of Plans

① Construction that must be notified to the Minister of Labor 30 days before construction begins

s51 Construction of bridges with a maximum span of 500m or more (suspension bridges 1000m) or more suspension bridge



B215



B419

(S52) Notification of Plans

(S52) Notification of Plans


3 Safety Management

3-3 Occupational Safety and Health

3.3.5 Notification of Plans

① Construction that must be notified to the Minister of Labor 30 days before construction begins

s52 Construction of tunnels over 3000m in length



T195

T16

(S53) Notification of Plans

(S53) Notification of Plans


3 Safety Management

3-3 Occupational Safety and Health

3.3.5 Notification of Plans

① Construction that must be notified to the Minister of Labor 30 days before construction begins

s53 Construction of tunnels over 1000m in length but less than 3000m
that involve excavating a shaft over 50m deep



T269

(S54) Notification of Plans

(S54) Notification of Plans

3 Safety Management


3-3 Occupational Safety and Health

3.3.5 Notification of Plans

① Construction that must be notified to the Minister of Labor 30 days before construction begins

s54 Construction involving compressed air work with a gauge pressure of 3kgf/cm² or more

pneumatic method



(S55) Notification of Plans


(S55) Notification of Plans

3 Safety Management

3-3 Occupational Safety and Health

3.3.5 Notification of Plans

- ② Construction that must be notified to the Chief of the Labor Standards Inspection Office
by 14 days before the start of construction
- s55 Construction or remodeling of buildings or structures over 31m in height



(S56) Notification of Plans

(S56) Notification of Plans

3 Safety Management

3-3 Occupational Safety and Health

3.3.5 Notification of Plans

② Construction that must be notified to the Chief of the Labor Standards Inspection Office
by 14 days before the start of construction


s56 Construction of bridges with a maximum span of 50m or more

Bridge erection (cantilever erection)



B167

cable-stayed bridge



B174

(S57) Notification of Plans

(S57) Notification of Plans


3 Safety Management

3-3 Occupational Safety and Health

3.3.5 Notification of Plans

② Construction that must be notified to the Chief of the Labor Standards Inspection Office
by 14 days before the start of construction

s57 Tunnel construction



(S58) Notification of Plans

(S58) Notification of Plans

3 Safety Management


3-3 Occupational Safety and Health

3.3.5 Notification of Plans

② Construction that must be notified to the Chief of the Labor Standards Inspection Office
by 14 days before the start of construction

s58 Excavation of natural ground with a height of 10m or more

- Provide berms every 5-10m in height



(S59) Notification of Plans

(S59) Notification of Plans

3 Safety Management


3-3 Occupational Safety and Health

3.3.5 Notification of Plans

② Construction that must be notified to the Chief of the Labor Standards Inspection Office by 14 days before the start of construction

s59 Construction using compressed air methods

Pneumatic method



F218

(S60) Notification of Plans

(S60) Notification of Plans


3 Safety Management

3-3 Occupational Safety and Health

3.3.5 Notification of Plans

③ Construction to be notified to the Chief of the Labor Standards Inspection Office
before construction begins

s60 Installation of track devices



(S61) Notification of Plans

(S61) Notification of Plans


3 Safety Management

3-3 Occupational Safety and Health

3.3.5 Notification of Plans

③ Construction to be notified to the Chief of the Labor Standards Inspection Office
before construction begins

s61 Formwork support (for structures with pillars 3.5m or higher in height)



(S62) Notification of Plans

(S62) Notification of Plans

3 Safety Management

3-3 Occupational Safety and Health


3.3.5 Notification of Plans

- ③ Construction to be notified to the Chief of the Labor Standards Inspection Office before construction begins

s62 Erected passage (passageway with height and length of 10m or more)

erection method of bent style

derick crane



B417

(S63) Notification of Plans

(S63) Notification of Plans

3 Safety Management


3-3 Occupational Safety and Health

3.3.5 Notification of Plans

- ③ Construction to be notified to the Chief of the Labor Standards Inspection Office
before construction begins

s63 Scaffolding (hanging scaffolding, overhanging scaffolding, scaffolding with height of 10m or more)

staging goliath erection



B201

(S64) Duties to be performed by specified principal contractors

(S64) Duties to be performed by specified principal contractors

3 Safety Management

3-3 Occupational Safety and Health

3.3.6 Duties to be performed by specified principal contractors

s64 Consultation organization Organization meetings

Specific principal business operator

Related contractors

Consultation organization Organization meetings
Meetings - Regular

(S65) Duties to be performed by specified principal contractors

(S65) Duties to be performed by specified principal contractors


3 Safety Management

3-3 Occupational Safety and Health

3.3.6 Duties to be performed by specified principal contractors

s65 Liaison and coordination

Communication and coordination



(S66) Duties to be performed by specified principal contractors

(S66) Duties to be performed by specified principal contractors


3 Safety Management

3-3 Occupational Safety and Health

3.3.6 Duties to be performed by specified principal contractors

s66 Workplace patrol

Communication and coordination



(S67) Duties to be performed by specified principal contractors

(S67) Duties to be performed by specified principal contractors


3 Safety Management

3-3 Occupational Safety and Health

3.3.6 Duties to be performed by specified principal contractors

s67 Guidance Safety and health education

Communication and coordination



(S68) Duties to be performed by specified principal contractors


(S68) Duties to be performed by specified principal contractors

3 Safety Management

3-3 Occupational Safety and Health

3.3.6 Duties to be performed by specified principal contractors

s68 Preparation of plans "Layout plans" for machinery and equipment, etc.



(S69) Duties to be performed by specified principal contractors

(S69) Duties to be performed by specified principal contractors


3 Safety Management

3-3 Occupational Safety and Health

3.3.6 Duties to be performed by specified principal contractors

s69 Signals Standardization of signals Crane operation

Communication and coordination




(S70) Scaffolding

(S70) Scaffolding

3 Safety management

3.4 Safety measures for assembling and dismantling scaffolding

3.4.1 Classification of scaffolding



(S71) Scaffolding


(S71) Scaffolding

3 Safety management

3.4 Safety measures for assembling and dismantling scaffolding

3.4.2 Scaffolding assembly and dismantling

s71 Inform all workers involved in the work content and procedures



B201

(S72) Scaffolding


(S72) Scaffolding

3 Safety management

3.4 Safety measures for assembling and dismantling scaffolding

3.4.2 Scaffolding assembly and dismantling

s72 Do not enter the work area except for relevant workers



(S73) Scaffolding


(S73) Scaffolding

3 Safety management

3.4 Safety measures for assembling and dismantling scaffolding

3.4.2 Scaffolding assembly and dismantling

s73 Stop work when danger is expected due to bad weather such as strong winds, heavy rain, heavy snow, etc.



(S74) Scaffolding


(S74) Scaffolding

3 Safety management

3.4 Safety measures for assembling and dismantling scaffolding

3.4.2 Scaffolding assembly and dismantling

s74 Scaffolding boards should be at least 20 cm high, and safety harnesses should be worn



(S75) Scaffolding


(S75) Scaffolding

3 Safety management

3.4 Safety measures for assembling and dismantling scaffolding

3.4.2 Scaffolding assembly and dismantling

s75 Use a hanging net or hanging bag to raise and lower materials, tools, etc.



(S76) Inspection of scaffolding


(S76) Inspection of scaffolding

3 Safety management

3.4 Safety measures for assembling and dismantling scaffolding

3.4.3 Inspection of scaffolding

s76 After strong winds, heavy rain, heavy snow, etc.



(S77) Inspection of scaffolding


(S77) Inspection of scaffolding

3 Safety management

3.4 Safety measures for assembling and dismantling scaffolding

3.4.3 Inspection of scaffolding

s77 After a moderate or greater earthquake



(S78) Inspection of scaffolding


(S78) Inspection of scaffolding

3 Safety management

3.4 Safety measures for assembling and dismantling scaffolding

3.4.3 Inspection of scaffolding

s78 In case of assembling, partially dismantling, or changing scaffolding



(S79) Inspection of scaffolding


(S79) Inspection of scaffolding

3 Safety management

3.4 Safety measures for assembling and dismantling scaffolding

3.4.3 Inspection of scaffolding

s79 Suspended scaffolding work



(S80) Scaffolding

(S80) Scaffolding


3 Safety management

③ The load capacity between the vertical supports is limited to 400kg

3.4 Safety measures for assembling and dismantling scaffolding

3.4.4 Main scaffolding

② Beam span 1.5m or less



(S81) Scaffolding

(S81) Scaffolding

3 Safety management

3.4 Safety measures for assembling and dismantling scaffolding

3.4.4 Main scaffolding

Materials used

(a) Steel pipe: Wall thickness is $1/24$ or more of the outer diameter. Material:

Tensile strength 38 kgf/mm²

(b) Joint fittings

(c) Fastening fittings




Fig. 3.4 Full scaffolding made of steel pipes

(S82) Scaffolding

(S82) Scaffolding

3 Safety management

3.4 Safety measures for assembling and dismantling scaffolding

3.4.5 One-sided scaffolding

① Overlap and join, overlap by 1m or more, and tie at least two places




Fig. 3.5 One-sided scaffolding made of logs

(S83) Scaffolding

(S83) Scaffolding

3 Safety management

3.4 Safety measures for assembling and dismantling scaffolding

3.4.6 Frame scaffolding

⑤ 150 kg or less per span

① Attach handrails within 90 cm

② Boards, width 25-80 cm

⑥ Vertical supports • floor spacing: 1.8 m or less

⑦ Width 30 cm or more
Install a ladder with a step spacing of 40 cm or less


③ 2 m or less for two-story buildings

④ Root ties


⑧ Frame with floor

⑨ Wall connection

Fig. 3.6 One-sided scaffolding made of steel pipes



(S84) Scaffolding



(S85) Scaffolding

(S85) Scaffolding

3 Safety management

3.4 Safety measures for assembling and dismantling scaffolding

3.4.6 Frame scaffolding

- ① Horizontal members must be provided on the top floor and every 5th floor or less




Fig. 3.8 Frame scaffolding

(S86) Scaffolding

(S86) Scaffolding

3 Safety management




3.4 Safety measures for assembling and dismantling scaffolding

3.4.7 Wall ties or braces

- Collapse prevention

Table 3.5 Wall tie spacing

Type	Vertical direction	Horizontal direction
Log scaffolding	5.5m or less	7.5m or less
Single pipe scaffolding	5.0m or less	5.5m or less
Frame scaffolding	9.0m or less	8.0m or less



(S87) Scaffolding

(S87) Scaffolding

3 Safety management

3.4 Safety measures for assembling and dismantling scaffolding

3.4.8 Work floor




Fig. 3.9 Work floor

(S88) Scaffolding

(S88) Scaffolding

3 Safety management


3.4 Safety measures for assembling and dismantling scaffolding

3.4.9 Suspended scaffolding

⑥ Suspended steel wire (safety factor 10 or more)

- ① For suspended wire rope
Safety factor 10 or more
Wire rope strands cut by 10% or less
Reduction in diameter by 7% or less of nominal diameter
No kinks, deformation, or corrosion

② Kink



⑦ Width 40cm or more, no gaps

④ Rollover approx. 1.5m

⑧ Secure firmly to prevent dislocation or falling off

- ⑤ For suspended chains
Safety factor 5 or more
Within 5% of initial elongation
Kink cross-sectional diameter 10% or less of nominal diameter
No cracks

⑨ Inspect suspended scaffolding before starting work

Fig. 3.10 Suspended scaffolding

(S89) Scaffolding

(S89) Scaffolding

3 Safety management

3.4 Safety measures for assembling and dismantling scaffolding

3-4-10 Ascending pier




Fig. 3-11 Ascending pier

(S90) Formwork and Shoring

(S90) Formwork and Shoring

3 Safety management


3.5 Safety measures for formwork and shoring

3.5.1 Materials

- ① No damage, deformation, or corrosion
- ② Main steel material Tensile strength 34kgf/mm² or more
- ③ Pipe support


Pipe thickness 2mm or more Single piece

End plate thickness 5.4mm or more Four or more bolt holes Steel end plate



S91

Fig. 3.12 Pipe support



S92

(S91) Formwork and Shoring

(S91) Formwork and Shoring

3 Safety management

3.5 Safety measures for formwork and shoring

3.5.1 Materials




Fig. 3.12 Pipe support

(S92) Formwork and Shoring

(S92) Formwork and Shoring

3 Safety management

3.5 Safety measures for formwork and shoring

3.5.1 Materials




Fig. 3.12 Pipe support

(S93) Formwork and Shoring

(S93) Formwork and Shoring

3 Safety management

3.5 Safety measures for formwork and shoring


3.5.2 Assembly, dismantling, and inspection

① Planning

① Creating an assembly diagram

② In case of a support is used alone

- Support: Do not exceed the maximum load



(S94) Formwork and Shoring

(S94) Formwork and Shoring


3 Safety management

3.5 Safety measures for formwork and shoring

3.5.2 Assembly, dismantling, and inspection

② Precautions for assembly and dismantling work

- ① No entry to the work area except for related workers
- ② Strong winds, heavy rain, heavy snow: Stop work
- ③ Use a hanging net or hanging bag to lift and lower materials, tools, etc.



(S95) Formwork and Shoring

(S95) Formwork and Shoring

3 Safety management

3.5 Safety measures for formwork and shoring


3.5.2 Assembly, dismantling, and inspection

③ Items to check in case of pouring concrete

① Check the formwork and shoring before starting work

② In case of an abnormality is found in the shoring during work

Be prepared to stop work



C1182
C1208
C1375


(S96) Formwork and Shoring

(S96) Formwork and Shoring

3 Safety management

3.5 Safety measures for formwork and shoring

3.5.3 Shoring using single-pipe columns



- ① Joints are butt joints or plug joints
- ② Joints are fastened using special fittings
- ③ Beams or joists
- ④ Columns
- ⑤ Bracing
- ⑥ Horizontal ties
- ⑦ Root ties
- ⑧ In case of placing beams or joists on the top end, secure them with steel end plates
- ⑨ Prevent displacement of horizontal ties
- ⑩ Install horizontal ties in two directions every 2m or less in height
- ⑪ Fix legs to prevent slipping
- ⑫ Prevent subsidence by using soffits, pouring concrete, driving piles, etc.

Figure 3.13 Shoring using single-pipe columns

(S97) Formwork and Shoring

(S97) Formwork and Shoring

3 Safety management

3.5 Safety measures for formwork and shoring

3.5.4 Shoring using pipe support columns




Fig. 3.14 Shoring using pipe support columns


(S98) Formwork and Shoring

(S98) Formwork and Shoring

3 Safety management

3.5 Safety measures for formwork and shoring

3.5.5 Shoring using steel pipe frame supports



- ① Install a horizontal frame on the top floor and every 5th floor or less
- ② Install horizontal ties in two directions on the top floor and every 5th floor or less, with 5 frames or less
- ③ Prevent displacement of horizontal ties with braces, etc.
- ④ In case of placing beams or joists, attach steel end plates and secure them to beams, etc.
- ⑤ Install cross braces

Fig. 3.15 Shoring using frame supports

(S99)Structure excavation-Structure - Excavation slope gradient- Soil quality

(S99)Structure excavation-Structure - Excavation slope gradient- Soil quality

Structure - Excavation slope - Soil quality

- Slope open cut method
- Excavation slope gradient
- Soil quality, excavation height, slope gradient

1 Types of geological formations


1-1 Bedrock Hard clay

2 Height of excavation surface

2-1 Less than 5m

3 Slope gradient of excavation surface

3-1 90° (1:0)




E401

(S100)Structure excavation-Structure - Excavation slope gradient- Soil quality

(S100)Structure excavation-Structure - Excavation slope gradient- Soil quality

Structure - Excavation slope - Soil quality

- Slope open cut method
- Excavation slope gradient
- Soil quality, excavation height, slope gradient



1 Types of geological formations

1-2 Others

2 Height of excavation surface

2-2 • Less than 2m • 2m or more but less than 5m • 5m or more

3 Slope gradient of excavation surface

3-2 Less than 90° (1:0) Less than 75° (1:0.268) Less than 60° (1:0.577)

(S101)Structure excavation-Structure - Excavation slope gradient- Soil quality

(S101)Structure excavation-Structure - Excavation slope gradient- Soil quality

Structure - Excavation slope - Soil quality

- Slope open cut method
- Excavation slope gradient
- Soil quality, excavation height, slope gradient

Sand

less than 5m in height

1 Types of geological formations Slope of excavation surface 35° (1:1.428) or less

1-3 Sand

2 Height of excavation surface 3 Slope gradient of excavation surface

2-3 Slope of excavation surface 35° (1:1.428) or less or less than 5m in height

E403

1 Types of geological formations Grounds that are susceptible


1-4 Grounds that are susceptible to collapse due to blasting, etc.

2 Height of excavation surface

2-4 Excavation surface slope 45° (1:1) or less or height less than 2m

3 Slope gradient of excavation surface

to collapse due to blasting, etc.



E404

(S102) Safety measures for excavation work

(S102) Safety measures for excavation work


3 Safety management

3.6 Safety measures for excavation work

3.6.1 Open excavation

excavation limits

ground	excavation surface height	slope gradient
A ground consisting of bedrock or hard clay	5m below	90° or less
	5m over	75° or less
Other geological formations	2m below	90° or less
	2-5m	75° or less
	5m over	60° or less
ground made of sand	5m below	35° or less
Rocks that are susceptible to collapse due to blasting, etc.	2m below	45° or less



The excavation surface is separated into horizontal stages of 2 m or more.

(S103) Safety measures for excavation work

(S103) Safety measures for excavation work

3 Safety management

3-6 Safety measures for excavation work




3-6-1 Open excavation

Do not open-cut in slits

Work inspection

Check for loose stones and cracks and their condition

- ① Before starting work that day
- ② After heavy rain or a moderate earthquake
- ③ After blasting



Work inspection

(S104) Safety measures for excavation work

(S104) Safety measures for excavation work

3 Safety management


3-6 Safety measures for excavation work

3-6-1 Open excavation

④ Working close to buried objects

Provide adequate protection for buried objects

Do not use excavation machinery if there is a risk of damage




(S105) Earth retaining support

(S105) Earth retaining support

3 Safety management

3-6 Safety measures for excavation work

3-6-2 Earth retaining support



Earth retaining timbering

① angle brace

② Sheet piles

③ Compressed materials: angle brace

The joint is a butt joint

④ the strut is supported by a structure,

it must be able to withstand the load.

⑤ Intermediate support column

⑥ strut

⑦ walling

⑧ Securely attach to sheet piles, piles,

and intermediate support columns

⑨ Connection of strut and angle brace

The intersection between the struts is tightened

with plate bolts.

Make it solid by welding, etc.

⑩ Inspection

- Period not exceeding 7 days
- In the case of an earthquake of medium or higher magnitude
- case of there is a risk of weakening of the ground due to heavy rain

(S106) Sheet pile installation

(S106) Sheet pile installation

3 Safety management

3-6 Safety measures for excavation work

3-6-3 Sheet pile installation

countermeasure




Figure 3-17 Safety measures for sheet piles

(S107) Sheet pile installation

(S107) Sheet pile installation

3 Safety management


3-6 Safety measures for excavation work

3-6-3 Sheet pile installation

countermeasure

loose sandy ground

This is caused by the difference in water level between the back and front of the sheet pile.
piping boiling




loose sandy ground

This is caused by the difference in water level between the back and front of the sheet pile.

Figure 3-17 Safety measures for sheet piles

(S108) Excavation of tunnels



(S109) Work platform

(S109) Work platform

3 Safety management

3.6 Safety measures for excavation work

3.6.5 Work platform




Fig. 3.19 Regulations for work platform

(S110) Specific machinery

(S110) Specific machinery


3 Safety management

3.7 Safety measures for construction machinery

3.7.1 Specific machinery


① Boiler

dipper dredger



R432
S40

② Lifting load of 3t or more




M138

③ Mobile crane with lifting




B111

④ Derrick with lifting load of 2t or more




B417

⑤ Elevator with lifting load of 1t or more




T112
F127

⑥ Construction lift with guide rail of 1.8m or more



S31

⑦ Gondola



B357

(S111) Vehicle-based construction machinery

(S111) Vehicle-based construction machinery

3 Safety management

3.7 Safety measures for construction machinery


3.7.3 Vehicle-based construction machinery

• Structure


① Equipped with headlights

② Equipped with sturdy head guards

• Speed limit: Set an appropriate speed limit



backhoe



Tractor excavator

(S112) Vehicle-based construction machinery

(S112) Vehicle-based construction machinery

3 Safety management

3.7 Safety measures for construction machinery

3.7.3 Vehicle-based construction machinery


- Things that drivers should observe

① In case of leaving the driving position

- Lower the bucket, zipper, and other work equipment to the ground
- Stop the engine and apply the travel brake


leaving the driving position

brake



backhoe

bucket



Tractor excavator

(S113) Vehicle-based construction machinery

(S113) Vehicle-based construction machinery

3 Safety management


3.7 Safety measures for construction machinery

3.7.3 Vehicle-based construction machinery

• Things that drivers should observe


② Do not allow anyone to ride in any seat other than the passenger seat

Do not allow anyone to ride




Mobility crane

B111



backhoe

bucket



bucket

Tractor excavator

(S114) Vehicle-based construction machinery

(S114) Vehicle-based construction machinery

3 Safety management


3.7 Safety measures for construction machinery

3.7.3 Vehicle-based construction machinery

- Things that drivers should observe


- ③ Observe the stability and maximum load capacity determined by the structure

maximum load




Mobility crane

B111



backhoe

bucket



bucket

Tractor excavator

(S115) Vehicle-based construction machinery

(S115) Vehicle-based construction machinery




3 Safety management

3.7 Safety measures for construction machinery


3.7.3 Vehicle-based construction machinery

- Things that drivers should observe

- ④ Establish certain signals and follow the instructions of the guide



B111



(S116) Vehicle-based construction machinery

(S116) Vehicle-based construction machinery

3 Safety management

3.7 Safety measures for construction machinery




3.7.3 Vehicle-based construction machinery

- Things that drivers should observe

⑤ Lifting loads with a power shovel

Do not use clamshells to lift workers, etc.

to lift workers



B111

(S117) Vehicle-based construction machinery

(S117) Vehicle-based construction machinery

3 Safety management



3.7 Safety measures for construction machinery

3.7.3 Vehicle-based construction machinery

- Transportation of vehicle-mounted construction machinery

① Loading and unloading should be done on a flat, solid surface

Loading and unloading
on a flat



B111

(S118) Vehicle-based construction machinery


(S118) Vehicle-based construction machinery

3 Safety management

3.7 Safety measures for construction machinery

3.7.3 Vehicle-based construction machinery

- Transportation of vehicle-mounted construction machinery
- ② In case of using flooring boards
 - Use ramps with sufficient length, width, and strength
 - Install securely with an appropriate gradient



(S119) Vehicle-based construction machinery

(S119) Vehicle-based construction machinery



3 Safety management

3.7 Safety measures for construction machinery

3.7.3 Vehicle-based construction machinery

- Transportation of vehicle-mounted construction machinery

- ③ In case of using embankments or temporary platforms,
ensure sufficient width, strength, and gradient



(S120) Specific voluntary inspections

(S120) Specific voluntary inspections

3 Safety management

3.7 Safety measures for construction machinery

3.7.4 Specific voluntary inspections

(vehicle-mounted construction machinery)

Table 3.8 Inspection of vehicle-mounted construction machinery


① Frequency	② Inspection items
③ Once per year	④ Prime mover and power transmission device ⑤ Running gear, steering gear, brakes ⑥ Working gear, hydraulic equipment, electrical system ⑦ Vehicle-related
⑧ Once per month	⑨ Presence or absence of brakes, clutches, steering gear, and working gear ⑩ Presence or absence of damage to wire ropes and chains ⑪ Presence or absence of damage to buckets, zippers, etc.
⑫ Before work begins	⑬ Presence or absence of brakes and clutches

(S121) Specific voluntary inspection

(S121) Specific voluntary inspection


- 3 Safety management
 - 3.7 Safety measures for construction machinery
 - 3.7.4 Specific voluntary inspection
 - vehicle-mounted construction machinery
 - Machines requiring specific voluntary inspection
 - ① Power press
 - ② Forklift
 - ③ Vehicle-mounted construction machinery
 - In case of raising the boom/arm for repairs,
set up safety posts/blocks to ensure safety

Power press




forklifts

repairs



Mobility crane



S22

S29

(S122) Pile drivers

(S122) Pile drivers

3 Safety management

3.7 Safety measures for construction machinery

3.7.5 Pile drivers

Key points: Measures to prevent collapse and wire rope safety

- ① Groove pulley
- ② Leave at least two turns on the winding body of the hoisting device
- ③ Wire rope: Safety factor 6 or higher, no joints, kicks, or damage
No more than 10% wire breakage
Reduction in diameter: no more than 7% of nominal diameter
- ④ Balance weight: Securely fixed to the frame
- ⑤ Always keep the installation area drained
- ⑥ Do not pull horizontally when taking in piles
- ⑦ In case of the ground is soft, use temporary laying plates and laying corners
In case of there is a risk of slipping, secure with piles and wedges




Figure 3.20 Safety measures for pile driving towers

M324

(S123) Mobile cranes

(S123) Mobile cranes

3 Safety management

3.7 Safety measures for construction machinery

3.7.6 Mobile cranes

Table 3.9 Periodic voluntary inspection

① Frequency	② Inspection items
③ Once per year	④ Load test
⑤ Once per month	⑥ Overwinding prevention devices, other safety devices, brakes and clutches, alarm devices, wire ropes, chains, hoisting equipment (hooks, grab buckets), wiring, switchboards and controllers
⑦ Before work begins	⑧ Overwinding prevention devices, alarm devices, brakes, clutches, controllers
⑨ Records of voluntary inspections to be kept for 3 years	

(S124) Mobile cranes

(S124) Mobile cranes

3 Safety management

3.7 Safety measures for construction machinery

3.7.6 Mobile Crane

- ① Do not exceed the range of the jib inclination angle
- ② Safety valve: Prevents the jib from overextending
- ③ Load obtained by subtracting the weight of the lifting equipment from the lifting load
- ④ Display the rated load and do not apply the load beyond the limit
- ⑤ Backstop: Prevents the jib from swinging
- ⑥ Do not allow workers to board unless the dedicated boarding device is sufficiently safe
- ⑦ Overload prevention devices should not be used unless they have a display of certification
- ⑧ The leader's feet should be similar to those of a pile driver or tower




Fig. 3.21 Precautions for Mobile Crane

(S125) Track system

(S125) Track system

3 Safety management

3.7 Safety measures for construction machinery


3.7.7 Track system

Vehicle operation method


① Method using a powered vehicle



② Method using a hoisting device



③ Method using human power (push)



(S126) Track system

(S126) Track system

3 Safety management

3.7 Safety measures for construction machinery

3.7.7 Track system

Vehicle operation method

① Method using a powered vehicle

① For hand-operated vehicles

- Install emergency stop devices

In case of used at an inclination angle of 30° or more

Install derailment prevention devices

② Improve visibility

③ Install headlights and warning bells

④ Spacing between side walls, etc.: 60cm or more

⑤ Weight of rail

⑥ Gradient: 50/1000 or less

⑦ Equip with manual brakes, and if over 10t,
also equip with powered brakes

⑧ Curved sections: Curve radius 10m or more,
install guard rails to maintain appropriate cant




Figure 3.22 Regulations for track equipment for powered vehicles

(S127) Track system

(S127) Track system

3 Safety management

3.7 Safety measures for construction machinery


3.7.7 Track system

Vehicle operation method

② Method using a hoisting device

- ① For drag cars, safety factor 6 or more
- ② For handcarts, safety factor 10 or more
- ③ Loss of number of wires 10% or less
- ④ No kinks or damage

② Method using a hoisting device



(S128) Track system

(S128) Track system

3 Safety management

3.7 Safety measures for construction machinery

3.7.7 Track system

Vehicle operation method

③ For hand-pushed vehicles

- ① The track must have a curve radius of 5m or more and a gradient of 1/15 or less
- ② An effective manual brake must be provided when the track has a gradient of 10/1000 or more
- ③ The vehicle speed must be 15km/h or less on a downward gradient

③ Method using human power (push)



(S129) Blasting work


(S129) Blasting work

3 Safety Management


3.8 Safety measures for blasting work

3.8.1 Handling explosives



- ① Containers must be made of wood or other electrically non-conductive materials



blasting



T38



T232

(S130) Blasting work

(S130) Blasting work


3 Safety Management

3.8 Safety measures for blasting work

3.8.1 Handling explosives

② Gunpowder, explosives, detonating cords, and pyrotechnics must be stored in separate containers

The same applies to transportation



(S131) Blasting work


(S131) Blasting work

3 Safety Management

3.8 Safety measures for blasting work

3.8.1 Handling explosives

- ③ The amount transported must be the amount used in one go



(S132) Blasting work

(S132) Blasting work


3 Safety Management

3.8 Safety measures for blasting work

3.8.1 Handling explosives

- ④ Frozen dynamite must not be melted in a dangerous manner such as direct contact with fire or hot objects

Melting must be done using a melter with hot water below 50° C or in a room below 30° C



(S133) Blasting work


(S133) Blasting work

3 Safety Management

3.8 Safety measures for blasting work

3.8.1 Handling explosives

- ⑤ In case of there is a risk of lightning, stop work related to electric detonators or electric fuses



(S134) Blasting work


(S134) Blasting work

3 Safety Management

3.8 Safety measures for blasting work

3.8.1 Handling explosives

- ⑥ Do not smoke or use fire near explosives



(S135) Blasting work

(S135) Blasting work


3 Safety Management

3.8 Safety measures for blasting work

3.8.1 Handling explosives

⑦ Temporary storage area for explosives

- A place where only those involved are needed
- A clean and dry place
- A place not exposed to direct sunlight




(S136) Blasting work

(S136) Blasting work

3 Safety Management


3.8 Safety measures for blasting work

3.8.2 Blasting Work




blasting

T141



T143

Dynamite detonator




facing (Cutting edge)

Fuse

clay tamping

T232



Drifter

① Drilling and Loading

① Do not use holes from the previous blasting

② Stop drilling when loading

③ No smoking or open flames in the vicinity

④ Loading materials must not contain pebbles with sharp edges

Other non-flammable materials must be used

⑤ Loading tools must be safe against friction, impact, and static electricity (e.g. wood - good, vinyl, metal - not good)

(S137) Blasting work


(S137) Blasting work

3 Safety Management

3.8 Safety measures for blasting work


3.8.2 Blasting Work

• Electric blasting




- ① Stop blasting in case of there is leakage (stray) current
- ② Ensure that a current of 1A or more flows through the circuit

• Safety measures during blasting



- No entry to dangerous areas
- Barricade
- Sign
- Sign with siren, etc.

• Fuse blasting



- Fuse
- Number of consecutive ignitions by the same person
- ① 1.5m or more, less than 10 shots
- ② 0.5-1.5m, less than 5 shots
- ③ 0.5m or less, 1 shot

Fig. 3-23 Precautions for blasting

(S138) Blasting work

(S138) Blasting work

3 Safety Management

3.8 Safety measures for blasting work


3.8.3 Post-blasting work

① After electric blasting

① Prevent re-ignition: Remove the blasting wire from the igniter and shorten its end

② Do not approach the loading area until more than 5 minutes have passed

Also, do not allow other workers to approach



(S139) Blasting work

(S139) Blasting work

3 Safety management

3-8 Safety measures for blasting work


3-8-3 Post-blasting work

② After blasting the fuse

① Check the number of ignitions

② Do not approach the loading area after 15 minutes have passed since blasting

Workers should not approach either



(S140) Blasting work

(S140) Blasting work


3 Safety management

3-8 Safety measures for blasting work

3-8-3 Post-blasting work

③ In case of there is unexploded explosives

- ① Drill parallel holes at least 60 cm apart from the unexploded blast hole, blast,
and collect the unexploded explosives
- ② Use a water stream from a rubber hose to flush out and collect the explosives and explosives
- ③ Remove the explosives, reload, and reignite



(S141) compressed air work

(S141) compressed air work

3 Safety management

3.9 Safety measures for compressed air work

3.9.1 Equipment

- Equipment defects: Causes oxygen deficiency

- ① Air supply pipe
- ② Check valve
- ③ Automatic alarm for abnormal temperature
- ④ Install a dedicated exhaust pipe
- ⑤ Man lock
- ⑥ Open flames strictly prohibited
- ⑥-1 Work room - Air volume is $4\frac{2}{3}$ /person or more
- ⑦ Floor area 0.3m^2 /person or more
Air volume 0.6m^3 /person or more
- ⑧ Shield
- ⑨ Material lock
- ⑩ Separate from man lock as much as possible




Fig. 3.24 Equipment for compressed air work

(S142) compressed air work

(S142) compressed air work

3 Safety management

3.9 Safety measures for compressed air work

3.9.2 Work management

- ① Pressurization and decompression speed: 0.80kgf/cm² per minute






Fig. 3.24 Equipment for compressed air work S141




② Shield method

F127
T112



Air pressure shield tunneling

T157



pneumatic method

T231

(S143) compressed air work

(S143) compressed air work

3 Safety management

3.9 Safety measures for compressed air work

3.9.2 Work management

- ② Workers undergo special health examinations once every six months






Fig. 3.24 Equipment for compressed air work
S141




② Shield method

F127
T112



Air pressure shield tunneling

T157



pneumatic method

T231

(S144) compressed air work

(S144) compressed air work

3 Safety management

3.9 Safety measures for compressed air work

3.9.2 Work management

- ③ For work inside a workroom or shaft where the pressure exceeds atmospheric pressure, a person with a high-pressure indoor work supervisor license must be selected

high-pressure indoor work supervisor license





Fig. 3.24 Equipment for compressed air work S141




② Shield method

F127
T112



Air pressure shield tunneling

T157



pneumatic method

T231

(S145) compressed air work

(S145) compressed air work

3 Safety management

3.9 Safety measures for compressed air work

3.9.2 Work management

- ④ To prevent burns, especially when under compressed air, take the following precautions
- Lights must be equipped with guards
 - Circuit switches: Use ones that do not scatter sparks around
 - Use heaters that do not become hot and become a source of ignition for flammable materials
 - Do not perform welding work
 - Do not bring in fire, match lighters, or other items that may cause fire







Fig. 3.24 Equipment for compressed air work
S141



Air pressure shield tunneling
T157



F127
T112



pneumatic method

T231

(S146)Caisson and Diving Box

(S146) Caisson and Diving Box

3 Safety management

3.9 Safety measures for compressed air work

3-9-3 Caisson and Diving Box

Blasting work inside the caisson should be done only after confirming

- ① Man lock
- ② Material lock
- ③ Inner diameter of exhaust pipe should be 53 mm or less
- ④ In case of exhausting and lowering the caisson, workers should evacuate to the outside
- ⑤ Shaft
- ⑥ Install equipment for safe ascent and descent
- ⑦ Air supply pipe
- ⑧ Direct piping without passing through shaft
- ⑨ Install electric bell and telephone for contact with the outside
- ⑩ Work room
- ⑪ Do not work when there is a risk of large amounts of water entering
- ⑫ Air volume should be 4 m³ or more per person
- ⑬ Do not enter the work room alone
- ⑭ Always measure oxygen concentration
- ⑮ Excavate 50 cm or less below the blade mouth
- ⑯ Height from the blade mouth to the ceiling should be 1.8 m or more




Figure 3-25 Safety measures for caisson construction F59

(S147)Electric Shock

(S147)Electric Shock

3 Safety management

3.10 Safety measures for electrical work

3.10.1 Measures to prevent electric shock

- ① Use holders that meet or exceed JIS standards
- ② Use automatic electric shock prevention devices for AC arc welding
- ③ Steel frame
- ④ AC arc welding at a height of 2m or more
- ⑤ Connect an electric shock circuit breaker to prevent electric shock
- ⑥ Equipped with a motor of 150V or more
- ⑦ Machinery and equipment




Fig. 3.27 Measures to prevent electric shock

(S148)Electric Shock

(S148)Electric Shock

3 Safety management

3.10 Safety measures for electrical work

3.10.1 Measures to prevent electric shock

Machinery and equipment

- ① Various regulations for preventing electric shock
- ② Wiring
- ③ Attach guards to hand-held lamps
- ④ Distribution boards
- ⑤ In case of wet with water or other fluids, use a coating with high insulating properties
- ⑥ Well pumps
- ⑦ Do not place on passageways




Fig. 3.27 Measures to prevent electric shock

(S149)Electric Shock

(S149)Electric Shock

3 Safety management

3.10 Safety measures for electrical work

3.10.1 Measures to prevent electric shock

Close-proximity work

- ① Wear insulating protective gear
if relocation is not possible
- ② Close-proximity distance
- ③ Have a supervisor
- ④ Follow signals
- ⑤ Close-proximity to live electrical circuits




Fig. 3.27 Measures to prevent electric shock

M393

(S150)Fall on

(S150)Fall on

3 Safety management

3・11 Safety measures for the fall disaster


3・11・1 Fall on

① In case of working at a height of 2m or more

① Set up a work platform

② In case of it is not possible to set up a platform, set up a protective net and have workers wear safety harnesses

③ Stop work if it is deemed dangerous due to bad weather



(S151)Fall on

(S151)Fall on

3 Safety management


3・11 Safety measures for the fall disaster

3・11・1 Fall on

② In case of working on a roof covered with slate or other materials

① Install a stepping board at least 30 cm wide to prevent being pierced

② Install safety netting



(S152)Fall on


(S152)Fall on

3 Safety management

3·11 Safety measures for the fall disaster

3·11·1 Fall on

- ③ Install equipment for safe ascent and descent in areas where the height or depth exceeds 1.5m



(S153)Fall on


(S153)Fall on

3 Safety management

3·11 Safety measures for the fall disaster

3·11·2 Dropping equipment

In case of dropping an object from a height of 3m or more,
appropriate dropping equipment must be provided.



(S154) oxygen deficiency

(S154) oxygen deficiency

3 Safety management



3.12 Measures against oxygen deficiency

3.12.1 Locations at risk of oxygen deficiency

A state in which the oxygen concentration in the air is less than 18%

The following strata are prone to oxygen deficiency

- Gravel layers with an impermeable layer above that contain little or no water or spring water
- Strata containing ferrous salts or manganous salts
- Sapropel layers
- Strata containing methane, ethane, or butane
- Strata that springs or contains carbonated water



(S155) oxygen deficiency

(S155) oxygen deficiency

3 Safety management

3.12 Measures against oxygen deficiency



3.12.2 Measures to prevent oxygen deficiency

① Measures to take when working inside wells, shafts, caissons, pits, etc.

that are in contact with the strata listed in the previous section or that connect to these strata

- Measure oxygen concentration at all times and keep records for three years
- Ventilate
- Evacuate immediately in the event of a power outage or ventilation interruption
- Use respirators, etc. if ventilation is not possible

② Conduct a preliminary investigation and take measures



(S156) Accommodation

(S156) Accommodation

3 Safety Management

3·13 Safety and Health Measures for the Accommodation

3·13·1 Safety and Health Measures for the Accommodation

① Install night lights in corridors and staircases

② Keep fire extinguishers on hand

③ Installation locations

- No dangerous substances (gas) nearby
- No harmful substances nearby
- No noise or vibration
- No avalanches or landslides
- No risk of flooding

④ Windows must be at least 1/7 of the floor area

⑤ Entrances and doors must open outwards,
at least two are required regardless
of the number of people

⑥ Staircases: 1 for less than 15 people
on the 2nd floor or higher
2 for 15 people or more




Figure 3-28: Safety in the accommodation

(S157) Accommodation

(S157) Accommodation

3 Safety Management

3 • 13 Safety and Health Measures for the Accommodation

3 • 13 • 2 Dormitory Rules

Dormitory rules must be shown to boarding workers

Rules that infringe on workers' freedom of private life, such as those in the following items, must not be made

1. Requiring approval from the employer for going out or staying out overnight
2. Forcing workers to participate in educational, recreational or other events
3. Restricting freedom of visitation




Figure 3-28: Safety in the accommodation

(S158) Accommodation

3 Safety Management

(S158) Accommodation

3-13 Safety and Health Measures for Dormitories

3-13-3 Dormitory Standards

① Corridor width

Bedrooms on both sides: 1.6m or more Other: 1.2m or more

② Corridor

③ Bedroom

④ Bedroom

⑤ Number of residents in each room: 16 or less

30 or less if there is a central passage of 75cm or more

Floor area: 2.5m²/person or more

Wooden floor height: 45cm or more

Ceiling height: 2.1m or more

Residents' names posted at the entrance

⑥ Dining room

⑦ Floors must be planked or concrete dining tables must be provided

Heating equipment must be provided

⑧ Rest room

⑨ Must be provided if 50 or more people are boarding at any one time

⑩ Toilet

⑪ Number of toilet stalls in the toilet: 1 or more for every 15 people or less

⑫ Bathhouse

⑬ Size must allow one person to bathe for every 10 people or less




Figure 3-29 Dormitory Standards




Figure 3-28: Safety in the accommodation

(S159) Public disaster

(S159) Public disaster

3 Safety management

3.14 Public disaster prevention measures

Construction in urban areas

S159① Worksites (division of worksites, fence standards, entrances and exits)

S160② Traffic measures (signs, safety lights, pedestrian measures, drainage, road surface maintenance)

S161③ Maintenance of tracks, etc. (prior consultation with track operators, insulation work, etc.)

S162④ Buried objects (safety measures, attendance, confirmation, etc.)

S163⑤ Retaining works (soil surveys, piles, beams, etc.)


S164⑥ Covering works (reconstruction plates, mounting surface, etc.)

S165⑦ Auxiliary methods (chemical injection method, groundwater lowering method)


S166⑧ Treatment of spring water, etc. (spring water and leaks, drainage treatment)

S167⑨ Treatment of residual soil, etc. (route, commissioning, operation management)

S168⑩ Backfilling



S173



S174

S159① Worksites (division of worksites, fence standards, entrances and exits)

(S160) Public disaster


(S160) Public disaster

3 Safety management

3.14 Public disaster prevention measures

Construction in urban areas

S160② Traffic measures (signs, safety lights, pedestrian measures, drainage, road surface maintenance)



(b) Under construction

(S161) Public disaster


(S161) Public disaster

3 Safety management

3.14 Public disaster prevention measures

Construction in urban areas

S161③ Maintenance of tracks, etc. (prior consultation with track operators, insulation work, etc.)



(S162) Public disaster


(S162) Public disaster

3 Safety management

3.14 Public disaster prevention measures

Construction in urban areas

S162④Buried objects (safety measures, attendance, confirmation, etc.)



(S163) Public disaster


(S163) Public disaster

3 Safety management

3.14 Public disaster prevention measures

Construction in urban areas

S163⑤ Retaining works (soil surveys, piles, beams, etc.)



(S164) Public disaster


(S164) Public disaster

3 Safety management

3.14 Public disaster prevention measures

Construction in urban areas

S164Ⓢ Covering works (reconstruction plates, mounting surface, etc.)



(S165) Public disaster





(S165) Public disaster

3 Safety management

3.14 Public disaster prevention measures

Construction in urban areas

S165⑦ Auxiliary methods (chemical injection method, groundwater lowering method)



Strainer (filtering wire mesh) (steel pipe) F92

(S166) Public disaster


(S166) Public disaster

3 Safety management

3.14 Public disaster prevention measures

Construction in urban areas

S166⑧ Treatment of spring water, etc. (spring water and leaks, drainage treatment)



(S167) Public disaster


(S167) Public disaster

3 Safety management

3.14 Public disaster prevention measures

Construction in urban areas

S167⑨ Treatment of residual soil, etc. (route, commissioning, operation management)



(S168) Public disaster

(S168) Public disaster

3 Safety management


3.14 Public disaster prevention measures

Construction in urban areas

① Construction of cut-and-cover shoring and frame foundation

② Structure construction/backfilling/shoring removal

③ Building the frame, backfilling, and pulling out the steel sheet piles



(S169) Public disaster

(S169) Public disaster


3 Safety management

3.14 Public disaster prevention measures

Construction in urban areas

Contact with nearby residents

① The developer (client) informs residents of the outline of the construction work and asks for their cooperation



(S170) Public disaster

(S170) Public disaster



3 Safety management

3.14 Public disaster prevention measures

Construction in urban areas
Contact with nearby residents

② The contractor will contact the developer and take into consideration the wishes of nearby residents

Regarding traffic regulations, do not interfere and make efforts to publicize



(S171) Public disaster

(S171) Public disaster


3 Safety management

3.14 Public disaster prevention measures

Construction in urban areas

Contact with nearby residents

The developer and contractor will immediately take emergency measures and contact relevant agencies
Promptly investigate the cause and prevent similar accidents from occurring



(S172) Workplace

(S172) Workplace

3 Safety Management

3.14 Public Accident Prevention Measures

3.14.2 Workplace

① Division of the workplace

Clear the boundaries with fixed fences, etc.

Clearly divide the installation locations of materials and machines




Figure 3.30 Standard diagram of fixed fence

(S173) Workplace

(S173) Workplace

3 Safety Management

3.14 Public Accident Prevention Measures

3.14.2 Workplace

② Fence specifications and dimensions

Fixed fence 1.2m or more

Moveable fence 0.8-1.0m

Length should be 1.00-1.50m

③ Fence coloring Fences should be colored with horizontal and 45° diagonal stripes of yellow and black.




Figure 3.30 Standard diagram of fixed fence


(S174) Workplace

(S174) Workplace

3 Safety Management

3.14 Public Accident Prevention Measures

3.14.2 Workplace



Example

↔ ⑧ Barricade

⊙ ⑨ Safety lights

△ ⑩ Safety cones

Ⓜ Caution: When working during the day, replace safety lights with safety cones

(a) In case of a slipway is provided

Fig. 3.31 How to Install a Mobile Fence


(S175) Workplace

(S175) Workplace

3 Safety Management

3.14 Public Accident Prevention Measures

3.14.2 Workplace




- Example
- 8 Barricade
 - ⊗ 9 Safety lights
 - △ 10 Safety cones

(b) In case of a slip-over section cannot be created

Fig. 3.31 How to Install a Mobile Fence

(S176)Traffic measures



(S177)Traffic measures

(S177)Traffic measures


3 Safety management

3/14 Public disaster prevention measures

3/14/3 Traffic Measures

1) Road signs: Signs will be installed according to the instructions of the road administrator and the chief of the local police station

2) Safety lights: For nighttime construction, safety lights will be installed that are about 1m high and have a brightness that can be seen from 150m ahead.





Road closure

Detour →



Road signs



The part facing the traffic

- Example
- ⑧ Barricade
 - ⊙ ⑨ Safety lights
 - △ ⑩ Safety cones



Road signs

(S178)Traffic measures


(S178)Traffic measures

3 Safety management


3/14 Public disaster prevention measures

3/14/3 Traffic Measures

③ Checking construction sites from a distance




Detour →



Road signs



Road signs



← Vehicle entrance/exit

S174

Example

- ⊂ ⑧ Barricade
- ⊙ ⑨ Safety lights
- △ ⑩ Safety cones

- Road signs
- Safety lights
- Signboards (internally illuminated)
- Luminous rotating lights
- Luminous rotating lights

(S179)Traffic measures

(S179)Traffic measures


3 Safety management

3/14 Public disaster prevention measures


3/14/3 Traffic Measures



④Traffic control near work sites

⑤Detours: In case of detours are necessary, follow the instructions of the road administrator and the police chief

 Construction area

 Detour

 Barricade

Detour 450m→

 Road closure





Figure 3/32 Traffic measures

National highway under construction

(S180)Traffic measures

(S180)Traffic measures

3 Safety management

3/14 Public disaster prevention measures

3/14/3 Traffic Measures

⑥ Road surface maintenance for vehicle traffic



In case of there is a step, make sure the slope is within 5%

⑦ Roadway width

3m for one lane

5.5m for two lanes

In case of the road becomes one lane due to construction, guides are posted



Example

- ⑧ Barricade
- ⑨ Safety lights
- ⑩ Safety cones

Fig. 3/32 Traffic Measures

(S181)Buried Objects

(S181)Buried Objects

3 Safety management

3/14 Public disaster prevention measures


3/14/4 Buried Objects

① Preliminary Safety Investigation

Developer: With the cooperation of the buried object manager, investigate the location, specifications, structure, and date of burial

In the design and specifications, etc., describe the measures necessary for the safety of the buried object and clearly indicate them to the contractor

Investigation



(S182)Buried Objects

(S182)Buried Objects



3 Safety management

3/14 Public disaster prevention measures

3/14/4 Buried Objects

② Attendance

Developer: In case of conducting the investigation, request the buried object manager to be present to confirm the location




(S183)Buried Objects

(S183)Buried Objects

3 Safety management

3/14 Public disaster prevention measures

3/14/4 Buried Objects



(S184)Buried Objects

(S184)Buried Objects

3 Safety management

3/14 Public disaster prevention measures

3/14/4 Buried Objects

⑤ Cloth digging and pot digging

Constructors must check that there are no buried objects when driving piles, sheet piles, etc., or drilling holes.

Probes must be carried out in conjunction with trial excavation up to about 2m from the location where buried objects are expected.

In case of buried objects are confirmed, dig cloth or pot digging is carried out to expose them.

Constructors




Figure 3-33 Cloth digging and pot digging

(S185)Buried Objects

(S185)Buried Objects

3 Safety management



3/14 Public disaster prevention measures

3/14/4 Buried Objects

⑥ Maintaining the security of exposed buried objects

Attach signs to exposed buried objects with the name, necessary security matters, contact information, etc.

In case of damage has already occurred, the contractor will contact the developer and manager and manager and request repair measures.



(S186)Buried Objects

(S186)Buried Objects



3 Safety management

3/14 Public disaster prevention measures

3/14/4 Buried Objects

⑦ Excavation in nearby areas

- Pay attention to loosening of the surrounding ground
- Take necessary measures to relocate or reinforce buried objects



(S187)Buried Objects


(S187)Buried Objects

3 Safety management

3/14 Public disaster prevention measures

3/14/4 Buried Objects

- ⑧ In case of using welding, cutting machines, etc. involving fire, check with a detector, etc., and take necessary measures to secure buried objects, such as heat shielding devices



(S188)Retaining Works




(S188)Retaining Works

3 Safety management


3/14 Public disaster prevention measures

3/14/5 Retaining Works

- ① Construct retaining works for depths of 1.5m or more
- ② Confirm the soil quality through soil surveys or existing documents and determine the construction method
- ③ Confirm safety through calculations to ensure stable retaining in adverse conditions such as rainfall



depths of 1.5m or more
Confirm safety



(S189) Retaining Works

(S189) Retaining Works


3 Safety management

3/14 Public disaster prevention measures

3/14/5 Retaining Works

④ Promptly backfill pot and cloth trenches after pouring

⑤ Use steel sheet piles in case of the soil is weak or the groundwater level is high



(S190)Retaining Works

(S190) Retaining Works


3 Safety management

3/14 Public disaster prevention measures

3/14/5 Retaining Works

- ⑥ The depth of the piles and steel sheet piles is 1.5m or more for piles and 3.0m or more for steel sheet piles

depth of the piles
piles -1.5m
steel sheet piles-3.0m



Earth retaining wall

(S191)Retaining Works



(S191)Retaining Works

3 Safety management

3/14 Public disaster prevention measures

3/14/5 Retaining Works

- ⑦ Parent Pile Horizontal Sheet Pile Method Earth Retaining Pile H-300 or more
Horizontal Sheet Pile Minimum Thickness 3cm or more



E245

(S192)Retaining Works

(S192)Retaining Works

3 Safety management

3/14 Public disaster prevention measures

3/14/5 Retaining Works


⑧ Steel sheet piles are Type III or higher as standard

⑨ The flaps should be in close contact with the columns or sheet piles,
and the members should be H-300 or higher

Spacing between joints is 6m or less

Vertical spacing is 3m or less

The first step should be 1m or less from the head



E244-E249

(S193)Covering work

(S193)Covering work

3 Safety management

3/14 Public disaster prevention measures

3/14/6 Covering work




Figure 3/34 Example of installation

(S194)Covering work

(S194)Covering work

3 Safety management

3/14 Public disaster prevention measures

3/14/6 Covering work

- ⑤ Bridge surface: Anti-slip material with a thickness of 2cm or more
- ⑥ Covering plate: Apply anti-slip material
- ⑦ Covering plate: Structure with no horizontal movement
- ⑧ Covering plate support beam: Maximum deformation: 2.5cm or less
- ⑨ Slope of 2.5% or more: Prevents support beam from collapsing





Figure 3/35 Example of reinforcement to prevent collapse F143

(S195)Gas disaster

(S195)Gas disaster

3 Safety management

3/15 Gas disaster prevention measures

3/15/1 Characteristics of harmful gases

1. Carbon monoxide (flammable, odorless, specific gravity 0.97)


0.02% → Headache

0.08% → Death in 2 hours

0.15% → Death in 1 hour


0.30% → Death in 30 minutes

Pneumatic caisson basics




F149

Tunnel (shot crete)



C1384
M400

Tunnel (pneumatic method)



T231

(S196)Gas disaster

(S196)Gas disaster

3 Safety management

3/15 Gas disaster prevention measures


3/15/1 Characteristics of harmful gases

② Carbon dioxide (nonflammable, odorless, specific gravity 1.53)

4% Nausea


10% Loss of consciousness

Pneumatic caisson basins




F149

Tunnel (shot crete)



C1384
M400

Tunnel (pneumatic method)



T231

(S197)Gas disaster

(S197)Gas disaster

3 Safety management

3/15 Gas disaster prevention measures


3/15/1 Characteristics of harmful gases

③Methane gas (flammable, tasteless, odorless, colorless, specific gravity 0.56)

Low toxicity


Water-soluble

Pneumatic caisson basics




F149

Tunnel(shot crete)



C1384
M400

Tunnel(pneumatic method)



T231

(S198)Gas disaster

(S198) Gas disaster

3 Safety management

3/15 Gas disaster prevention measures


3/15/1 Characteristics of harmful gases

3/15/2 Explosive properties of harmful gases

Explosive limits


Symbols	Gas name	Explosive limit
CO	Carbon monoxide	12.5%-74%
CH ₄	Methane	5.4%-14%
C ₃ H ₈	Propane	2.2%-9.5%

Pneumatic caisson basics




F149

Tunnel (shot crete)



C1384
M400

Tunnel (pneumatic method)



T231

(S199)Gas disaster

(S199) Gas disaster

3 Safety management


3/15 Gas disaster prevention measures

3/15/1 Characteristics of harmful gases

3/15/3 Explosive generation of harmful gases


- ① Optical combustible gas measuring device - Danger level of mixed gas of 2 or more types -
Direct reading possible
- ② Ventilation
- ③ Do not bring open flames into the mine
- ④ In case of loading, use 2 or more people
- ⑤ Evacuate workers when concentration is 30% or more of the lower explosion limit
- ⑥ Organic solvents enter the respiratory system in the form of gas, and also enter through the skin

Pneumatic caisson basics




F149

Tunnel (shot crete)



C1384 M400

Tunnel (pneumatic method)



T231

(S200)Workplace accidents

(S200)Workplace accidents


6. Safety management

6.1. Workplace accidents

6.1.2. Workplace accidents in the construction industry

- Dump cars (28%)

- Construction machinery (24%)






E331
M4

- Landslides (16%)




E537



100
E232

- Scaffolding accidents (13%)



B201

(S201)Workplace accidents

(S201)Workplace accidents

- 6 Safety Management
- 6.1 Workplace Accidents
- 6.1.4 Causes of Accidents




Figure 6-1 Causes and countermeasures of disasters

(S202)Workplace accidents

(S202)Workplace accidents

6 Safety Management

6.1 Workplace Accidents


6.1.4 Causes of Accidents

① Structural defects - Countermeasures: careful design and construction

① Structural defects - Countermeasures: careful design and construction

② Equipment defects - adequate maintenance

③ Lack of budget - appropriate budget



② Human factors (incomplete actions)

① Ignorance, immaturity, carelessness - Countermeasures: Utilizing training systems

② Physical fatigue - Countermeasures: Health management

③ Management factors (defects)

Figure 6-1 Causes and countermeasures of disasters

(S203)Workplace accidents

(S203)Workplace accidents

6 Safety Management

6.1 Workplace Accidents


6.1.4 Causes of Accidents

① Structural defects - Countermeasures: careful design and construction

① Structural defects - Countermeasures: careful design and construction

② Equipment defects - adequate maintenance

③ Lack of budget - appropriate budget



② Human factors (incomplete actions)

① Ignorance, immaturity, carelessness - Countermeasures: Utilizing training systems

② Physical fatigue - Countermeasures: Health management

③ Management factors (defects)

① Lack of education - Countermeasures: Education and training

② Lack of work meetings - Countermeasures: Communicating work content: Proper allocation

Figure 6-1 Causes and countermeasures of disasters

(S204) Safety management


(S204) Safety management

6 Safety management

6/1 Workplace accidents

6/1/5 Implementation of Safety management



- ① Safety education
- ② Stimulating safety awareness
- ③ Standardization of work
- ④ Machine inspection and maintenance



① Safety education

② Understanding of work content

③ Use of safety helmets and safety harnesses



S74

Figure 6/2 Safety management

(S205)Safety management


(S205) Safety management

6 Safety management

6/1 Workplace accidents

6/1/5 Implementation of Safety management

- ① Safety education
- ② Stimulating safety awareness
- ③ Standardization of work
- ④ Machine inspection and maintenance



- ② Stimulating safety awareness
 - ① Presentation of improvement ideas
 - ② Safety week
 - ③ Badges and safety awards




Figure 6/2 Safety management

(S206)Safety management

(S206) Safety management

6 Safety management

6/1 Workplace accidents

6/1/5 Implementation of Safety management

- ① Safety education
- ② Stimulating safety awareness
- ③ Standardization of work
- ④ Machine inspection and maintenance




Figure 6/2 Safety management

(S207) Safety management


(S207) Safety management

6 Safety management

6/1 Workplace accidents


6/1/5 Implementation of Safety management

- ① Safety education
- ② Stimulating safety awareness
- ③ Standardization of work
- ④ Machine inspection and maintenance




- ④ Machine inspection and maintenance
 - ① Inspection of scaffolding and ground
 - ② Machine inspection and maintenance


Inspection



scaffolding



ground



Towed scraper

scrape dozer

motor scraper

Excavator

backhoe

drag line

clamshell

Tractor excavator + dump truck

Figure 6/2 Safety management

(S208) Safety management

(S208) Safety management


6 Safety management

6.2 Safety management plan

6.2.1 Consideration of the work environment

① Measures for poorly ventilated areas

- Ventilation measures
- Measures to prevent dust scattering



(S209) Safety management

(S209) Safety management



6 Safety management

6.2 Safety management plan

6.2.1 Consideration of the work environment

② Places where intense noise is generated

- Inform workers of the noise generation and clearly indicate the location
- Use protective equipment such as earplugs at noise generating areas and for workers



F38

(S210) Safety management

(S210) Safety management

6 Safety management


6.2 Safety management plan

6.2.1 Consideration of the work environment


③ Tasks that require measurement of the work environment

- Places where dust is emitted
- Measure the ventilation volume, temperature, and carbon dioxide concentration in a work area inside a mine with ventilation facilities
- Measure the oxygen and hydrogen sulfide concentrations in places where there is a risk of oxygen deficiency

Measure the oxygen and hydrogen sulfide



S15



F43

S36

(S211) Safety management


(S211) Safety management

6 Safety Management

6.2 Safety Management Plan

6.2.2 Measures to prevent harm around the construction site

- ① Install protective structures such as fences to prohibit entry to the construction area
 - Install and maintain fall prevention measures, construction signs, and night lighting



(S212) Safety management


(S212) Safety management

6 Safety Management

6.2 Safety Management Plan

6.2.2 Measures to prevent harm around the construction site

- ② Fix detour and sign boards to prevent them from falling over due to wind, etc.
 - Thorough maintenance and inspection are performed to make them easily visible to pedestrians



(S213) Safety management

(S213) Safety management


6 Safety Management

6.2 Safety Management Plan

6.2.2 Measures to prevent harm around the construction site

③ To prevent traffic accidents near the entrances and exits of the construction site

- Lower the sidewalk, take measures to prevent slipping, and install buzzers or yellow rotating lights at the entrances and exits of construction vehicles



Example

→ ⑧ Barricade

⊙ ⑨ Safety lights

△ ⑩ Safety cones

- ③
- Road signs
 - Safety lights
 - Signboards (internally illuminated)
 - Luminous rotating lights
 - Luminous rotating lights

③ Vehicle entrance/exit

S174

S178

(S214) Safety management

(S214) Safety management



6 Safety Management

6.2 Safety Management Plan


6.2.2 Measures to prevent harm around the construction site

④ Measures to prohibit entry


- Display specific details of the dangers
- Clearly state that entering without protective equipment will cause health problems or dangers




fences S173



construction signs



S179



prohibit entry

S174 S211

(S215) Safety management

(S215) Safety management


6. Safety management

6.2. Safety management plan

6.2.3. Fall prevention measures

① To prevent falls from scaffolding and walkways, install work floors and handrails at heights of 2m or more.

- In case of there are no handrails, install protective nets and have workers use safety harnesses. height of 2m or more
- appropriate dropping equipment must be provided.
equipment for safe ascent and descent



S153
S75

(S216) Safety management


(S216) Safety management

6. Safety management

6.2. Safety management plan

6.2.3. Fall prevention measures

- ② In case of assembling and dismantling scaffolding and steel frames, install equipment such as life ropes so that safety harnesses can be used easily.



(S217) Safety management


(S217) Safety management

6. Safety management

6.2. Safety management plan

6.2.3. Fall prevention measures

③ Always perform safety inspections and maintenance management.



(S218) Safety management


(S218) Safety management

6. Safety management

6.2. Safety management plan

6.2.3. Fall prevention measures

- ④ In case of working at night, ensure that there is sufficient light and illumination, and maintain a state where there are no tripping hazards, steps, or punctures.



(S219) Safety management

(S219) Safety management

⑤ To prevent falls
handrails
protective nets
supervisor.

6. Safety management

6.2. Safety management plan

6.2.3. Fall prevention measures

⑤ To prevent falls from work floors and openings, use handrails, protective nets, and safety harnesses. When removing fences, prohibit workers

from entering and assign a supervisor.

appropriate dropping equipment must be provided. height of 2m or more
equipment for safe ascent and descent life ropes

working at night
sufficient light and
illumination
no tripping hazards, steps

Scaffolding


Handrails, protective nets

Do not enter
No entry measures

hanging bag



Stop work



safety harnesses

safety inspections and maintenance management.

dropping equipment

Fall prevention
Scaffolding/passageway
Handrails, protective nets
safety harnesses

S153
S75

(S220) Safety management

(S220) Safety management


6. Safety management

6.2. Safety management plan

6.2.3. Fall prevention measures

- ⑥ As a fall prevention measure during excavation work, install protective nets and use safety harnesses when shaping the slope by hand.

Fall prevention measures: Install fences, set up temporary walkways, and do not allow workers to walk on support materials.



To prevent falls
life ropes
protective nets
safety harnesses
fences
temporary walkways

(S221) Prevent falling objects


(S221) Prevent falling objects

6. Safety Management

6.2. Safety Management Plan

6.2.4. Measures to prevent falling objects

- ① Measures to prevent falling objects shall be taken at the top of external scaffolding and entrances/exits of structures, and safe passageways shall be designed.



(S222) Prevent falling objects


(S222) Prevent falling objects

6. Safety Management

6.2. Safety Management Plan

6.2.4. Measures to prevent falling objects

- ② In case of protective nets/sheets are removed, measures to prohibit entry shall be taken and promptly restored.



(S223) Prevent falling objects


(S223) Prevent falling objects

6. Safety Management

6.2. Safety Management Plan

6.2.4. Measures to prevent falling objects

- ③ Nets shall be used according to purpose, and damaged or disarrayed ones shall not be used.



(S224) Prevent falling objects


(S224) Prevent falling objects

6. Safety Management

6.2. Safety Management Plan

6.2.4. Measures to prevent falling objects

- ④ In case of close to roads or residential areas, measures to prevent falling objects shall be taken at the site.



(S225) Prevent falling objects


(S225) Prevent falling objects

6. Safety Management

6.2. Safety Management Plan

6.2.4. Measures to prevent falling objects

- ⑤ In case of installing fall equipment, installation shall be made at heights of 3m or more, measures to prohibit entry shall be taken, and chutes for dropping objects and dust chutes shall be provided.




(S226) Prevent falling objects

6. Safety Management (S226) Prevent falling objects

6.2. Safety Management Plan

6.2.4. Measures to prevent falling objects

- ⑥ In case of accumulating materials for high-altitude work, do not accumulate within 1m of work floors, openings, or shoulders, and when temporarily storing scattered objects, store them in boxes or tie them down tightly, and tie off plywood or other items that are easily blown away by the wind with ropes, etc.



(S227) Prevent falling objects

(S227) Prevent falling objects


6. Safety Management

6.2. Safety Management Plan

6.2.4. Measures to prevent falling objects

⑦ As a means of communication and coordination when working above and below, thoroughly devise a process and avoid working above and below.

- Measures to prevent falling objects shall be taken



(S228) Mobile crane


(S228) Mobile crane

6. Safety management

6.2. Safety management plan

6.2.5. Safety measures for mobile crane work

- ① In case of planning and selecting a mobile crane, check the hook weight, lifting load, and working radius
- Take insulation protection measures near power lines,
 - Plan to work with a designated safety distance



S124
M393

(S229) Mobile crane


(S229) Mobile crane

6. Safety management

6.2. Safety management plan

6.2.5. Safety measures for mobile crane work

- ② In case of placing and installing, take into consideration ground reaction forces.
 - Use a floor plate and floor angle to prevent tipping
 - Install the outriggers fully extended
 - Work while strictly adhering to the rotation range and restrictions



(S230) Mobile crane

(S230) Mobile crane


6. Safety management

6.2. Safety management plan

6.2.5. Safety measures for mobile crane work

③ Signals and guidance for mobile cranes - Signaller: 1 person

Signals: Work halfway with a clear view of the operator Do it outside the radius



(S231) Mobile crane

(S231) Mobile crane


6. Safety management

6.2. Safety management plan

6.2.5. Safety measures for mobile crane work

④ Mobile crane work - points to note

- ① Stop the load when it is above the ground
check the position of the center of gravity
the state of the sling



S124
M393

(S232) Mobile crane

(S232) Mobile crane


6. Safety management

6.2. Safety management plan

6.2.5. Safety measures for mobile crane work

④ Mobile crane work – points to note

② Make sure the hook is directly above the center of gravity of the load



S124
M393

(S233) Mobile crane

(S233) Mobile crane


6. Safety management

6.2. Safety management plan

6.2.5. Safety measures for mobile crane work

④ Mobile crane work - points to note

③ In case of lifting, the boom will bend and the hook position will move so work slightly inside the working radius



S124
M393

(S234) Mobile crane

(S234) Mobile crane


6. Safety management

6.2. Safety management plan

6.2.5. Safety measures for mobile crane work

④ Mobile crane work - points to note

④ Make sure there are no people or obstacles around the turning radius



(S235) Mobile crane

(S235) Mobile crane


6. Safety management

6.2. Safety management plan

6.2.5. Safety measures for mobile crane work

④ Mobile crane work - points to note

- ⑤ In case of lowering the load, do not land all at once, stop just before it hits the floor and lower it quietly



(S236) Mobile crane

(S236) Mobile crane

6. Safety management

6.2. Safety management plan


6.2.5. Safety measures for mobile crane work

④ Mobile crane work - points to note

⑥ No entry measures

Do not allow people to enter the working radius while working with a mobile crane

Inform workers with signs, etc.



S124
M393

(S237) Public accidents

(S237) Public accidents


6.3 Guidelines for preventing public accidents during construction work (civil engineering)

In case of a contractor carries out construction work in an urban area

Minimum technical matters


① Workplace: Workplace classification, fence standards, entrances and exits

①
fence



S173

①
Workplace



S174

S159

(S238) Public accidents

(S238) Public accidents

6.3 Guidelines for preventing public accidents during construction work (civil engineering)

In case of a contractor carries out construction work in an urban area

Minimum technical matters




Figure 3/32 Traffic measures

National highway under construction

(S239) Public accidents


(S239) Public accidents

6・3 Guidelines for preventing public accidents during construction work (civil engineering)

In case of a contractor carries out construction work in an urban area

Minimum technical matters

③ Maintenance of tracks, etc.: Prior consultation with track managers, insulation work



S161
H510

(S240) Public accidents


(S240) Public accidents

6.3 Guidelines for preventing public accidents during construction work (civil engineering)

In case of a contractor carries out construction work in an urban area

Minimum technical matters

④Buried objects: Safety treatment, attendance, confirmation



F128

S162

(S241) Public accidents


(S241) Public accidents

6 • 3 Guidelines for preventing public accidents during construction work (civil engineering)

In case of a contractor carries out construction work in an urban area

Minimum technical matters

⑤ Retaining works: Soil survey, piles, beams



S163

F161

(S242) Public accidents

(S242) Public accidents


6.3 Guidelines for preventing public accidents during construction work (civil engineering)

In case of a contractor carries out construction work in an urban area

Minimum technical matters

⑥ Covering works: Covering plates, surface of mounting parts

⑥ Covering works



F143
S164

(S243) Public accidents

(S243) Public accidents

6.3 Guidelines for preventing public accidents during construction work (civil engineering)




In case of a contractor carries out construction work in an urban area

Minimum technical matters

⑦ Auxiliary methods: Chemical injection, groundwater lowering method

⑦ Auxiliary methods

Well point construction method




Vacuum pumping



Electropenetration method

current flow (direct current)



Strainer (filtering wire mesh) (steel pipe) F92

S165

(S244) Public accidents


(S244) Public accidents

6.3 Guidelines for preventing public accidents during construction work (civil engineering)

In case of a contractor carries out construction work in an urban area

Minimum technical matters

⑧ Treatment of spring water, etc.: Spring water and leaks, drainage treatment



E416-E419
S166

(S245) Public accidents


(S245) Public accidents

6.3 Guidelines for preventing public accidents during construction work (civil engineering)

In case of a contractor carries out construction work in an urban area

Minimum technical matters

⑨ Treatment of residual soil, etc.: Route, consignment, operation management



(S246) Public accidents

(S246) Public accidents

6 • 3 Guidelines for preventing public accidents during construction work (civil engineering)

In case of a contractor carries out construction work in an urban area


Minimum technical matters

⑩ Backfilling

① Construction of cut-and-cover shoring and frame foundation

② Structure construction/backfilling/shoring removal

③ Building the frame, backfilling, and pulling out the steel sheet piles



S168

F361

(S247) Public accidents

(S247) Public accidents


6.3 Guidelines for preventing public accidents during construction work (civil engineering)

In case of a contractor carries out construction work in an urban area

Minimum technical matters


- ① Others: Machinery, electricity, shields, tunneling work, work at height, formwork support, prevention of fire and oxygen deficiency

① oxygen deficiency




F43
S36

① work at height



B502

① oxygen deficiency



G1051
M420